



## Features:

- Protections: Short circuit / Overload / Over voltage
- Cooling by free air convection
- LED indicator for power on
- 100% full load burn-in test
- Withstand 300VAC surge input for 5 second
- Withstand 5G vibration test
- High efficiency, long life and high reliability
- 3 years warranty

## **SPECIFICATION**



MODEL		RT-125A			RT-125B			RT-125C			RT-125D			
	OUTPUT NUMBER	CH1	CH2	CH3	CH1	CH2	CH3	CH1	CH2	CH3	CH1	CH2	CH3	
ОИТРИТ	DC VOLTAGE	5V	12V	-5V	5V	12V	-12V	5V	15V	-15V	5V	24V	12V	
	RATED CURRENT	12A	5.5A	1A	12A	5A	1A	10A	4.5A	1A	8A	3A	2A	
	CURRENT RANGE Note.6	2 ~ 15A	0.5 ~ 6A	0.1 ~ 1A	2 ~ 15A	0.5 ~ 6A	0.1 ~ 1A	2 ~ 15A	0.5 ~ 6A	0.1 ~ 1A	2 ~ 15A	0.4 ~ 4A	0.1 ~ 2A	
	RATED POWER Note.6	131W			132W			132.5W			136W			
	RIPPLE & NOISE (max.) Note.2	80mVp-p   120mVp-p   80mVp-p		80mVp-p 120mVp-p 120mVp-p		80mVp-p 150mVp-p 150mVp-p			80mVp-p 150mVp-p 120mVp-p					
	VOLTAGE ADJ. RANGE	CH1: 4.75 ~ 5.5V			CH1: 4.75 ~ 5.5V			CH1: 4.75 ~ 5.5V			CH1: 4.75 ~ 5.5V			
	VOLTAGE TOLERANCE Note.3	±2.0%	+8,-3%	+6,-10%	±2.0%	+8,-3%	±6.0%	±2.0%	+8,-3%	±6.0%	±2.0%	±5.0%	±6.0%	
	LINE REGULATION Note.4	±0.5%	±1.0%	±1.0%	±0.5%	±1.0%	±1.0%	±0.5%	±1.0%	±1.0%	±0.5%	±1.0%	±1.0%	
	LOAD REGULATION Note.5	±1.0%	±3.0%	±6.0%	±1.0%	±3.0%	±6.0%	±1.0%	±3.0%	±6.0%	±1.0%	±3.0%	±6.0%	
	SETUP, RISE TIME	500ms, 20ms/230VAC 1200ms, 30ms/115VAC at full load								•				
	HOLD UP TIME (Typ.)	25ms/230VAC 30ms/115VAC at full load												
INPUT	VOLTAGE RANGE	88 ~ 132VAC / 176 ~ 264VAC selected by switch 248 ~ 373VDC(Withstand 300VAC surge for 5sec. Without damage)												
	FREQUENCY RANGE	47 ~ 63Hz												
	EFFICIENCY (Typ.)	79%			80%	80%			81%			82%		
	AC CURRENT (Typ.)	3A/115VAC 2A/230VAC												
	INRUSH CURRENT (Typ.)	COLD START 40A/230VAC												
	LEAKAGE CURRENT	<2mA / 240VAC												
PROTECTION		110 ~ 150% rated output power												
	OVERLOAD	Protection type : Hiccup mode, recovers automatically after fault condition is removed												
		CH1: 5.75 ~ 6.75V												
	OVER VOLTAGE	Protection type : Hiccup mode, recovers automatically after fault condition is removed												
ENVIRONMENT	WORKING TEMP.	-25 ~ +70 $^{\circ}$ C (Refer to output load derating curve)												
	WORKING HUMIDITY	20 ~ 90% RH non-condensing												
	STORAGE TEMP., HUMIDITY	-40 ~ +85℃, 10 ~ 95% RH												
	TEMP. COEFFICIENT	±0.03%/°(	$\pm 0.03\%$ /°C (0 ~ 50°C)on +5V output											
	VIBRATION	10 ~ 500H	10 ~ 500Hz, 5G 10min./1cycle, period for 60min. each along X, Y, Z axes											
SAFETY & EMC (Note 7)	SAFETY STANDARDS	UL60950-	UL60950-1, TUV EN60950-1 approved											
	WITHSTAND VOLTAGE	I/P-O/P:3KVAC I/P-FG:1.5KVAC O/P-FG:0.5KVAC												
	ISOLATION RESISTANCE	I/P-O/P, I/P-FG, O/P-FG:100M Ohms / 500VDC / 25°C / 70% RH												
	EMI CONDUCTION & RADIATION	Compliance to EN55022 (CISPR22) Class B												
	HARMONIC CURRENT	Compliance to EN61000-3-2,-3												
	EMS IMMUNITY	Compliance to EN61000-4-2,3,4,5,6,8,11; ENV50204, EN61000-6-2 (EN50082-2), heavy industry level, criteria A												
OTHERS	MTBF	209.3Khrs	min. M	IL-HDBK-2	17F (25°C)									
	DIMENSION	199*98*38mm (L*W*H)												
	PACKING	0.7Kg; 20	pcs/14Kg/0	.8CUFT										
NOTE	All parameters NOT specia     Ripple & noise are measure     Tolerance: includes set up     Line regulation is measure     Load regulation is measure     Each output can work within     The power supply is conside EMC directives. For guidan (as available on http://www.     Length of set up time is me	ed at 20Mb tolerance, d from low d from 20% n current ra lered a con ice on how meanwell.	Iz of bando line regula line to high 6 to 100% ange. But to ponent what to perform com)	width by us ation and lo a line at rate rated load total output hich will be a these EM	sing a 12" to add regulation in the control of the	wisted pair on. output at 6 't exceed r oto a final e ease refer t	-wire terming 60% rated atted outpure equipment. To "EMI testing for the second control of the second control	nated with load. t power. The final e ting of con	a 0.1uf & a	47uf paralle must be re ower supplie	-confirmed	that it still	meets	
		8. Length of set up time is measured at cold first start. Turning ON/OFF the power supply very quickly may lead to increase of the set up time.  File Name: RT-125-SPEC 2010-1												



