PRIMETEST 250

A comprehensive handheld PAT tester. The Engineer's ideal companion.



Seaward's lightweight, portable Primetest 250 PAT tester is unique in its range of safety tests. The PrimeTest 250 will perform all of the tests required by the IEE Code of Practice, including RCD trip, protective conductor current and touch current where required. The unit also includes a 250V DC insulation test suitable for testing sensitive electrical appliances and surge protected leads.

The PrimeTest 250 is ideal for ensuring that all workplace electrical equipment does not pose a danger to users -including three-phase machinery. As a result, 3-phase industrial plant and equipment used in factories, workshops, schools and colleges can all be tested safely and effectively.

The unique range of tests incorporated in this lightweight and highly versatile instrument means that most workplace appliances can be tested using long life battery power. However, when protective conductor current or touch current measurements are required, simply connecting a mains supply will automatically select the correct test sequence.

The Primetest 250 is designed for ease of use and carries out all electrical safety tests against pre-set limits with measured test results and clear PASS/FAIL indication on a large display.

The PrimeTest 250 is an easy-to-use tester which is ideal for those who need to test a wide range of electrical equipment.

*For 3 phase and RCD testing, accessories are required.

Key Features

- Easy to use manual PAT tester
- Comprehensive range of tests
- Clear PASS/FAIL indication
- Capable of both equivalent leakage (using battery power) and protective conductor / touch current (using mains power)
- Lightweight
- Automatic test sequences

Ideal Users

- In-house safety testing engineers
- Electrical Contractors
- Service & Maintenance Engineers



Seaward

Bracken Hill, South West Industrial Estate, Peterlee, SR8 2SW

Tel: +44 (0) 191 5863511 **Fax:** +44 (0) 191 5860227

PRIMETEST 250 SPECIFICATIONS

SPECIFICATIONS

Earth continuity

200mA minimum into 2Ω Output Current:

Test Voltage (o/c): 9V DC nominal Test Duration (Class I Test): 2s nominal

Display Range: 0.01 ohm to 19.99 ohm

Pass Value (Class I Test): 0.2Ω

Insulation resistance

Test Voltage: 250/500VDC @1mA nominal, < 2mA (s/c)

Test Duration (Class I or II): 2s Display Range:

0.01 Mohm to 19.99 Mohm

Pass Value: $1.0~\text{M}\Omega~\text{Class I}$

 $2.0~\text{M}\Omega$ Class II

Equivalent leakage

Test Voltage: 40V Nominal AC 50Hz Open Circuit

Test Duration: 2s – 30s nominal Display Range: 0.1 mA to 19.99mA 0.75mA CLI / 0.25mA CL II Pass Value:

IEC lead test

Test voltage: 5V DC nominal Test Duration: Time for test (2s max)

Live / Neutral Checks for o/c, s/c and crossed Test:

Protective Conductor Current

Test Voltage: Supply Voltage, max current 13A

Test Duration: 30s maximum

Display Range: 0.15 mA to 9.99 mA

Pass Value: 0.75mA/3.5mA (user selectable with 0.75mA as default)

Touch current

Test Voltage: Supply Voltage, max current 13A

Test Duration: 30s maximum Display Range: 0.10 mA to 5.00 mA

Pass Value: 0.25mA

3 phase differential leakage current *Requires 3 phase adaptor accessory

Test Voltage: 3 phase supply voltage Test Duration: Continuous measurement Display Range: 0.10 mA to 9.99 mA

Pass Value: 3.5mA

RCD trip time

Test Voltage: Mains supply voltage Test Current: 10mA / 30mA rms sinusoidal

Test Current Phase: 0°/180° auto switched on alternate tests

Measuring Range: 0ms - 500ms Pass Value: 200ms

Power socket check

Input voltage range: Indicates configuration of voltage potential:-

225 - 254V AC max current 13A UK

Line potential phase to earth

Line potential phase to neutral Line potential neutral to earth



CLARE

Seaward test and measurement companies include:



