# DATA SHEET



# PCA9553 4-bit I<sup>2</sup>C-bus LED driver with programmable blink rates

Product data sheet Supersedes data of 2004 Oct 01





## 4-bit I<sup>2</sup>C-bus LED driver with programmable blink rates

PCA9553



#### **FEATURES**

- 4 LED drivers (on, off, flashing at a programmable rate)
- 2 selectable, fully programmable blink rates (frequency and duty cycle) between 0.172 Hz and 44 Hz (5.82 and 0.023 seconds)
- Input/outputs not used as LED drivers can be used as regular GPIOs
- Internal oscillator requires no external components
- I<sup>2</sup>C-bus interface logic compatible with SMBus
- Internal power-on reset
- Noise filter on SCL/SDA inputs
- 4 open drain outputs directly drive LEDs to 25 mA
- Controlled edge rates to minimize ground bounce
- No glitch on power-up
- Supports hot insertion
- Low stand-by current
- Operating power supply voltage range of 2.3 V to 5.5 V
- 0 to 400 kHz clock frequency
- ESD protection exceeds 2000 V HBM per JESD22-A114,
   150 V MM per JESD22-A115 and 1000 V CDM per JESD22-C101
- Latch-up testing is done to JEDEC Standard JESD78 which exceeds 100 mA
- Packages offered: SO8, TSSOP8 (MSOP8), HVSON8

#### **DESCRIPTION**

The PCA9553 LED Blinker blinks LEDs in I<sup>2</sup>C-bus and SMBus applications where it is necessary to limit bus traffic or free up the I<sup>2</sup>C-bus master's (MCU, MPU, DSP, chipset, etc.) timer. The uniqueness of this device is the internal oscillator with two programmable blink rates. To blink LEDs using normal I/O

Expanders like the PCF8574 or PCA9554, the bus master must send repeated commands to turn the LED on and off. This greatly increases the amount of traffic on the I<sup>2</sup>C-bus and uses up one of the master's timers. The PCA9553 LED Blinker instead requires only the initial set-up command to program BLINK RATE 1 and BLINK RATE 2 (i.e., the frequency and duty cycle). From then on, only one command from the bus master is required to turn each individual open drain output ON, OFF, or to cycle at BLINK RATE 1 or BLINK RATE 2. Maximum output sink current is 25 mA per bit and 100 mA per package.

Any bits not used for controlling the LEDs can be used for General Purpose Parallel Input/Output (GPIO) expansion.

Power-On Reset (POR) initializes the registers to their default state, all zeroes, causing the bits to be set HIGH (LED off).

Due to pin limitations, the PCA9553 is not featured with hardware address pins. The PCA9553/01 and the PCA9553/02 have different fixed I<sup>2</sup>C-bus addresses allowing operation of both on the same bus.

#### **PIN CONFIGURATION**




Figure 1. Pin configuration

#### **PIN DESCRIPTION**

PIN NUMBER	SYMBOL	FUNCTION
1	LED0	LED driver 0
2	LED1	LED driver 1
3	LED2	LED driver 2
4	V <sub>SS</sub>	supply ground
5	LED3	LED driver 3
6	SCL	serial clock line
7	SDA	serial data line
8	$V_{DD}$	supply voltage

#### ORDERING INFORMATION

PACKAGES	TEMPERATURE RANGE	ORDER CODE	TOPSIDE MARK	DRAWING NUMBER
8-pin plastic SO	–40 °C to +85 °C	PCA9553D/01	P9553/1	SOT96-1
8-pin plastic SO	–40 °C to +85 °C	PCA9553D/02	P9553/2	SOT96-1
8-pin plastic TSSOP (MSOP)	–40 °C to +85 °C	PCA9553DP/01	P53/1	SOT505-1
8-pin plastic TSSOP (MSOP)	–40 °C to +85 °C	PCA9553DP/02	P53/2	SOT505-1
8-pin plastic HVSON	-40 °C to +85 °C	PCA9553TK	P53	SOT908-1

Standard packing quantities and other packaging data are available at www.standardics.philips.com/packaging. PCA9553TK uses version /01 address.

## 4-bit I<sup>2</sup>C-bus LED driver with programmable blink rates

PCA9553

#### **BLOCK DIAGRAM**




Figure 2. Block diagram

## 4-bit I<sup>2</sup>C-bus LED driver with programmable blink rates

PCA9553

#### **DEVICE ADDRESSING**

Following a START condition the bus master must output the address of the slave it is accessing. The address of the PCA9553/01 is shown in Figure 3 and PCA9553/02 in Figure 4.

PCA9553TK uses the version /01 address.




Figure 3. Slave address — PCA9553/01




Figure 4. Slave address — PCA9553/02

The last bit of the address byte defines the operation to be performed. When set to logic 1 a read is selected, while a logic 0 selects a write operation.

#### **CONTROL REGISTER**

Following the successful acknowledgement of the slave address, the bus master will send a byte to the PCA9553 which will be stored in the Control Register.




Figure 5. Control register

The lowest 3 bits are used as a pointer to determine which register will be accessed.

If the auto-increment flag is set, the three low order bits of the Control Register are automatically incremented after a read or write. This allows the user to program the registers sequentially. The contents of these bits will rollover to '000' after the last register is accessed.

When auto-increment flag is set (AI = 1) and a read sequence is initiated, the sequence must start by reading a register different from '0' (B2 B1 B0  $\neq$  0 0 0)

Only the 3 least significant bits are affected by the Al flag.

Unused bits must be programmed with zeroes.

#### **Control Register definition**

В2	B1	B0	REGISTER NAME	TYPE	REGISTER FUNCTION
0	0	0	INPUT	read	input register
0	0	1	PSC0	read/write	frequency prescaler 0
0	1	0	PWM0	read/write	PWM register 0
0	1	1	PSC1	read/write	frequency prescaler 1
1	0	0	PWM1	read/write	PWM register 1
1	0	1	LS0	read/write	LED selector

#### **REGISTER DESCRIPTION**

#### **INPUT — INPUT REGISTER**

					LED 3	LED 2	LED 1	LED 0
bit	7	6	5	4	3	2	1	0
default	0	0	0	0	Χ	Х	Х	Х

The INPUT register reflects the state of the device pins. Writes to this register will be acknowledged but will have no effect.

**NOTE:** The default value "X" is determined by the externally applied logic level, normally '1' when used for directly driving LED with pull-up to  $V_{DD}$ .

#### **PSC0** — FREQUENCY PRESCALER 0

bit	7	6	5	4	3	2	1	0
default	1	1	1	1	1	1	1	1

PSC0 is used to program the period of the PWM output.

The period of BLINK0 =  $\frac{(PSC0 + 1)}{44}$ 

#### PWM0 — PWM REGISTER 0

bit	7	6	5	4	3	2	1	0
default	1	0	0	0	0	0	0	0

The PWM0 register determines the duty cycle of BLINK0. The outputs are LOW (LED off) when the count is less than the value in PWM0 and HIGH when it is greater. If PWM0 is programmed with 00h, then the PWM0 output is always LOW.

The duty cycle of BLINK0 is:  $\frac{256 - PWM0}{256}$ 

#### **PSC1** — FREQUENCY PRESCALER 1

bit	7	6	5	4	3	2	1	0
default	1	1	1	1	1	1	1	1

PSC1 is used to program the period of PWM output.

The period of BLINK1 =  $\frac{(PSC1 + 1)}{44}$ 

#### PWM1 — PWM REGISTER 1

bit	7	6	5	4	3	2	1	0
default	1	0	0	0	0	0	0	0

The PWM1 register determines the duty cycle of BLINK1. The outputs are LOW (LED off) when the count is less than the value in PWM1 and HIGH when it is greater. If PWM1 is programmed with 00h, then the PWM1 output is always LOW.

The duty cycle of BLINK1 is:  $\frac{256 - PWM1}{256}$ 

## 4-bit I<sup>2</sup>C-bus LED driver with programmable blink rates

PCA9553

#### LS0 — LED SELECTOR

	LED3		LED2		LED 1		LED 0	
bit	7	6	5	4	3	2	1	0
default	0	1	0	1	0	1	0	1

The LSx LED select registers determine the source of the LED data.

00 = Output is set LOW (LED on)

01 = Output is set high-impedance (LED off – default)

10 = Output blinks at PWM0 rate

11 = Output blinks at PWM1 rate

#### PINS USED AS GENERAL PURPOSE I/Os

LED pins not used to control LEDs can be used as general purpose I/Os.

For use as input: Set LEDx to high-impedance (01) and then read the pin state via the input register.

For use as output: Connect external pull-up resistor to the pin and size it according to the DC recommended operating characteristics. LED output pin is HIGH when the output is programmed as high-impedance, and LOW when the output is programmed LOW through the "LED selector" register. The output can be pulse-width controlled when PWM0 or PWM1 are used.

#### **POWER-ON RESET**

When power is applied to  $V_{DD}$ , an internal Power-On Reset (POR) holds the PCA9553 in a reset condition until  $V_{DD}$  has reached  $V_{POR}$ . At this point, the reset condition is released and the PCA9553 registers are initialized to their default states, with all outputs in the off state. Thereafter,  $V_{DD}$  must be lowered below 0.2 V to reset the

## 4-bit I<sup>2</sup>C-bus LED driver with programmable blink rates

PCA9553

#### CHARACTERISTICS OF THE I2C-BUS

The I<sup>2</sup>C-bus is for 2-way, 2-line communication between different ICs or modules. The two lines are a serial data line (SDA) and a serial clock line (SCL). Both lines must be connected to a positive supply via a pull-up resistor when connected to the output stages of a device. Data transfer may be initiated only when the bus is not busy.

#### Bit transfer

One data bit is transferred during each clock pulse. The data on the SDA line must remain stable during the HIGH period of the clock pulse as changes in the data line at this time will be interpreted as control signals (see Figure 6).




Figure 6. Bit transfer

#### Start and stop conditions

Both data and clock lines remain HIGH when the bus is not busy. A HIGH-to-LOW transition of the data line, while the clock is HIGH is defined as the start condition (S). A LOW-to-HIGH transition of the data line while the clock is HIGH is defined as the stop condition (P) (see Figure 7).

#### System configuration

A device generating a message is a transmitter: a device receiving is the receiver. The device that controls the message is the master and the devices which are controlled by the master are the slaves (see Figure 8).




Figure 7. Definition of start and stop conditions




Figure 8. System configuration

## 4-bit I<sup>2</sup>C-bus LED driver with programmable blink rates

PCA9553

#### **Acknowledge**

The number of data bytes transferred between the start and the stop conditions from transmitter to receiver is not limited. Each byte of eight bits is followed by one acknowledge bit. The acknowledge bit is a HIGH level put on the bus by the transmitter whereas the master generates an extra acknowledge related clock pulse.

A slave receiver which is addressed must generate an acknowledge after the reception of each byte. Also a master must generate an acknowledge after the reception of each byte that has been clocked out of the slave transmitter. The device that acknowledges has to pull down the SDA line during the acknowledge clock pulse, so that the SDA line is stable LOW during the HIGH period of the acknowledge related clock pulse, set-up and hold times must be taken into account.

A master receiver must signal an end of data to the transmitter by not generating an acknowledge on the last byte that has been clocked out of the slave. In this event, the transmitter must leave the data line HIGH to enable the master to generate a stop condition.




Figure 9. Acknowledgement on the I<sup>2</sup>C-bus

## 4-bit I<sup>2</sup>C-bus LED driver with programmable blink rates

PCA9553

#### **Bus transactions**




Figure 10. Write to register





Figure 11. Read from register



#### NOTES:

- 1. This figure assumes the command byte has previously been programmed with 00h.
- 2. PCA9553/01 shown.

Figure 12. Read input port register

## 4-bit I<sup>2</sup>C-bus LED driver with programmable blink rates

PCA9553

#### APPLICATION DATA




Figure 13. Typical application

#### Minimizing I<sub>DD</sub> when the I/O is used to control LEDs

When the I/Os are used to control LEDs, they are normally connected to  $V_{DD}$  through a resistor as shown in Figure 13. Since the LED acts as a diode, when the LED is off the I/O  $V_{IN}$  is about 1.2 V less than  $V_{DD}$ . The supply current,  $I_{DD}$ , increases as  $V_{IN}$  becomes lower than  $V_{DD}$  and is specified as  $\Delta I_{DD}$  in the DC characteristics table.

Designs needing to minimize current consumption, such as battery power applications, should consider maintaining the I/O pins greater than or equal to  $V_{DD}$  when the LED is off. Figure 14 shows a high value resistor in parallel with the LED. Figure 15 shows  $V_{DD}$  less than the LED supply voltage by at least 1.2 V. Both of these methods maintain the I/O  $V_{IN}$  at or above  $V_{DD}$  and prevents additional supply current consumption when the LED is off.




Figure 14. High value resistor in parallel with the LED




Figure 15. Device supplied by a lower voltage

## 4-bit I<sup>2</sup>C-bus LED driver with programmable blink rates

PCA9553

#### **Programming example**

The following example will show how to set LED0 and LED1 off. It will then set LED2 to blink at 1 Hz, 50% duty cycle. LED3 will be set to blink at 4 Hz, 25% duty cycle. PCA9553/01 is used in this example.

Table 1.

	I <sup>2</sup> C-bus
Start	S
PCA9553 address	C4h
PSC0 subaddress + auto-increment	11h
Set prescaler PSC0 to achieve a period of 1 second:	2Bh
Blink period = $1 = \frac{PSCO + 1}{44}$	
PSC0 = 43	
Set PWM0 duty cycle to 50%:	80h
$\frac{256 - PWM0}{256} = 0.5$	
PWM0 = 128	
Set prescaler PWM1 to achieve a period of	0Ah
0.25 seconds: Blink period = $0.25 = \frac{PSC1 + 1}{44}$	
PSC1 = 10	
Set PWM1 output duty cycle to 25%:	C0h
$\frac{256 - PWM1}{256} = 0.25$	
PWM1 = 192	
Set LED0 on, LED1 off, LED2 set to blink at PSC0, PWM0, LED3 set to blink at PCS1, PWM1	E4h
Stop	Р

## 4-bit I<sup>2</sup>C-bus LED driver with programmable blink rates

PCA9553

#### **ABSOLUTE MAXIMUM RATINGS**

In accordance with the Absolute Maximum Rating System (IEC 134)

SYMBOL	PARAMETER	CONDITIONS	MIN	MAX	UNIT
$V_{DD}$	Supply voltage		-0.5	6.0	V
V <sub>I/O</sub>	DC voltage on an I/O		V <sub>SS</sub> - 0.5	5.5	V
I <sub>I/O</sub>	DC output current on an I/O		_	±25	mA
I <sub>SS</sub>	Supply current			100	mA
P <sub>tot</sub>	Total power dissipation			400	mW
T <sub>stg</sub>	Storage temperature range		-65	+150	°C
T <sub>amb</sub>	Operating ambient temperature		-40	+85	°C

#### **HANDLING**

Inputs and outputs are protected against electrostatic discharge in normal handling. However, to be totally safe, it is desirable to take precautions appropriate to handling MOS devices. Advice can be found in Data Handbook IC24 under "Handling MOS devices".

#### DC CHARACTERISTICS

 $V_{DD}$  = 2.3 V to 5.5 V;  $V_{SS}$  = 0 V;  $T_{amb}$  = -40 °C to +85 °C; unless otherwise specified. TYP at 3.3 V and 25 °C.

SYMBOL	PARAMETER	CONDITIONS	MIN	TYP	MAX	UNIT
Supplies	•	•	•		•	
$V_{DD}$	Supply voltage		2.3	_	5.5	V
I <sub>DD</sub>	Supply current	Operating mode; $V_{DD} = 5.5 \text{ V}$ ; no load; $V_{I} = V_{DD}$ or $V_{SS}$ ; $f_{SCL} = 100 \text{ kHz}$	_	350	500	μΑ
I <sub>stb</sub>	Standby current	Standby mode; $V_{DD}$ = 5.5 V; no load; $V_{I}$ = $V_{DD}$ or $V_{SS}$ ; $f_{SCL}$ = 100 kHz	_	1.9	3.0	μΑ
Δl <sub>DD</sub>	Additional standby current	Standby mode; V <sub>DD</sub> = 5.5 V; Every LED I/O at V <sub>IN</sub> = 4.3 V; f <sub>SCL</sub> = 0 kHz	_	_	325	μА
V <sub>POR</sub>	Power-on reset voltage (Note 1)	No load; V <sub>I</sub> = V <sub>DD</sub> or V <sub>SS</sub>	_	1.7	2.2	V
Input SCL;	input/output SDA					
$V_{IL}$	LOW-level input voltage		-0.5	_	0.3V <sub>DD</sub>	V
V <sub>IH</sub>	HIGH-level input voltage		0.7V <sub>DD</sub>	_	5.5	V
I <sub>OL</sub>	LOW-level output current	V <sub>OL</sub> = 0.4 V	3	6.5	_	mA
ΙL	Leakage current	$V_I = V_{DD} = V_{SS}$	-1	_	+1	μΑ
C <sub>I</sub>	Input capacitance	$V_I = V_{SS}$	_	3.7	5	pF
I/Os						
$V_{IL}$	LOW-level input voltage		-0.5	_	0.8	V
V <sub>IH</sub>	HIGH-level input voltage		2.0	_	5.5	V
		V <sub>OL</sub> = 0.4 V; V <sub>DD</sub> = 2.3 V; Note 2	9	_	_	mA
		V <sub>OL</sub> = 0.4 V; V <sub>DD</sub> = 3.0 V; Note 2	12		_	mA
	LOW loved and and and	V <sub>OL</sub> = 0.4 V; V <sub>DD</sub> = 4.5 V; Note 2	15		_	mA
l <sub>OL</sub>	LOW-level output current	V <sub>OL</sub> = 0.7 V; V <sub>DD</sub> = 2.3 V; Note 2	15	_	_	mA
		V <sub>OL</sub> = 0.7 V; V <sub>DD</sub> = 3.0 V; Note 2	20		_	mA
		V <sub>OL</sub> = 0.7 V; V <sub>DD</sub> = 4.5 V; Note 2	25	_	_	mA
ΙL	Input leakage current	$V_{DD} = 3.6 \text{ V}; V_{I} = 0 \text{ V or } V_{DD}$	-1	_	1	μΑ
C <sub>IO</sub>	Input/output capacitance			2.1	5	pF

#### NOTES:

<sup>1.</sup>  $V_{DD}$  must be lowered to 0.2 V in order to reset part.

<sup>2.</sup> Each I/O must be externally limited to a maximum of 25 mA and the device must be limited to a maximum current of 100 mA.

## 4-bit I<sup>2</sup>C-bus LED driver with programmable blink rates

PCA9553

#### **AC SPECIFICATIONS**

SYMBOL	PARAMETER		RD MODE BUS	FAST MO I <sup>2</sup> C-BU	UNITS		
		MIN	MAX	MIN	MAX	1	
f <sub>SCL</sub>	Operating frequency	0	100	0	400	kHz	
t <sub>BUF</sub>	Bus free time between STOP and START conditions	4.7	_	1.3	_	μs	
t <sub>HD;STA</sub>	Hold time after (repeated) START condition	4.0	_	0.6	_	μs	
t <sub>SU;STA</sub>	Repeated START condition set-up time	4.7	_	0.6	_	μs	
t <sub>SU;STO</sub>	Set-up time for STOP condition	4.0	<u> </u>	0.6	_	μs	
t <sub>HD;DAT</sub>	Data in hold time	0	<u> </u>	0	_	ns	
t <sub>VD;ACK</sub>	Valid time for ACK condition <sup>2</sup>	T -	600	_	600	ns	
t <sub>VD;DAT</sub> (L)	Data out valid time <sup>3</sup>	_	600	_	600	ns	
t <sub>VD;DAT</sub> (H)	DAT (H) Data out valid time <sup>3</sup>		1500	_	600	ns	
t <sub>SU;DAT</sub>	Data set-up time	250	_	100	_	ns	
t <sub>LOW</sub>	Clock LOW period	4.7	_	1.3	_	μs	
t <sub>HIGH</sub>	Clock HIGH period	4.0	<u> </u>	0.6	_	μs	
t <sub>F</sub>	Clock/Data fall time	T -	300	20 + 0.1 C <sub>b</sub> <sup>1</sup>	300	ns	
t <sub>R</sub>	Clock/Data rise time	<u> </u>	1000	20 + 0.1 C <sub>b</sub> <sup>1</sup>	300	ns	
t <sub>SP</sub>	t <sub>SP</sub> Pulse width of spikes that must be suppressed by the input filters		50	_	50	ns	
Port Timing							
t <sub>PV</sub>	Output data valid		200		200	ns	
t <sub>PS</sub>	Input data set-up time	100	_	100	_	ns	
t <sub>PH</sub>	Input data hold time	1	_	1	_	μs	

#### NOTES:

- C<sub>b</sub> = total capacitance of one bus line in pF.
   t<sub>VD;ACK</sub> = time for Acknowledgement signal from SCL LOW to SDA (out) LOW.
   t<sub>VD;DAT</sub> = minimum time for SDA data out to be valid following SCL LOW.

## 4-bit I<sup>2</sup>C-bus LED driver with programmable blink rates

PCA9553




Figure 16. Typical frequency variation over process at  $V_{DD}$  = 2.3 V to 3.0 V




Figure 17. Typical frequency variation over process at  $V_{DD}$  = 3.0 V to 5.5 V

## 4-bit I<sup>2</sup>C-bus LED driver with programmable blink rates

PCA9553




Figure 18. Definition of timing




Figure 19. I<sup>2</sup>C-bus timing diagram; rise and fall times refer to V<sub>IL</sub> and V<sub>IH</sub>





Figure 20. Test circuitry for switching times

## 4-bit I<sup>2</sup>C-bus LED driver with programmable blink rates

PCA9553

#### SO8: plastic small outline package; 8 leads; body width 3.9 mm

SOT96-1



#### DIMENSIONS (inch dimensions are derived from the original mm dimensions)

UNIT	A max.	Α1	A <sub>2</sub>	A <sub>3</sub>	bp	С	D <sup>(1)</sup>	E <sup>(2)</sup>	е	HE	L	Lp	Q	v	w	у	Z <sup>(1)</sup>	θ
mm	1.75	0.25 0.10	1.45 1.25	0.25	0.49 0.36	0.25 0.19	5.0 4.8	4.0 3.8	1.27	6.2 5.8	1.05	1.0 0.4	0.7 0.6	0.25	0.25	0.1	0.7 0.3	8°
inches	0.069	0.010 0.004	0.057 0.049	0.01		0.0100 0.0075	0.20 0.19	0.16 0.15	0.05	0.244 0.228	0.041	0.039 0.016	0.028 0.024	0.01	0.01	0.004	0.028 0.012	0°

#### Notes

- 1. Plastic or metal protrusions of 0.15 mm (0.006 inch) maximum per side are not included.
- 2. Plastic or metal protrusions of 0.25 mm (0.01 inch) maximum per side are not included.


OUTLINE		EUROPEAN	ISSUE DATE				
VERSION	IEC	JEDEC	JEITA		PROJECTION	ISSUE DATE	
SOT96-1	076E03	MS-012				<del>99-12-27</del> 03-02-18	


## 4-bit I<sup>2</sup>C-bus LED driver with programmable blink rates

PCA9553

TSSOP8: plastic thin shrink small outline package; 8 leads; body width 3 mm

SOT505-1





#### DIMENSIONS (mm are the original dimensions)

UNIT	A max.	A <sub>1</sub>	A <sub>2</sub>	A <sub>3</sub>	bp	C	D <sup>(1)</sup>	E <sup>(2)</sup>	e	HE	L	Lp	٧	w	у	Z <sup>(1)</sup>	θ
mm	1.1	0.15 0.05	0.95 0.80	0.25	0.45 0.25	0.28 0.15	3.1 2.9	3.1 2.9	0.65	5.1 4.7	0.94	0.7 0.4	0.1	0.1	0.1	0.70 0.35	6° 0°

#### Notes

- 1. Plastic or metal protrusions of 0.15 mm maximum per side are not included.
- 2. Plastic or metal protrusions of 0.25 mm maximum per side are not included.


OUTLINE		EUROPEAN	ISSUE DATE			
VERSION	IEC	JEDEC	JEITA	PROJECTION	ISSUE DATE	
SOT505-1					<del>-99-04-09-</del> 03-02-18	

## 4-bit I<sup>2</sup>C-bus LED driver with programmable blink rates

PCA9553

## HVSON8: plastic thermal enhanced very thin small outline package; no leads; 8 terminals; body 3 $\times$ 3 $\times$ 0.85 mm

SOT908-1



1. Plastic or metal protrusions of 0.075 mm maximum per side are not included.

OUTLINE		REFER	RENCES	EUROPEAN	ISSUE DATE		
VERSION	IEC	JEDEC	JEITA		PROJECTION	ISSUE DATE	
SOT908-1		MO-229				<del>05-09-26</del> 05-10-05	

## 4-bit $I^2C$ -bus LED driver with programmable blink rates

PCA9553

#### **REVISION HISTORY**

Rev	Date	Description
_4	20060818	Product data sheet. Supersedes data of 2004 Oct 01 (9397 750 13728).
		Modifications:
		"Features" section on page 2:     — last bullet: added "HVSON8"
		Ordering information table on page 2: added "HVSON8" package offering.
		"Device addressing" section on page 4: added second paragraph.
		Package outlines: added HVSON8 package outline drawing SOT908-1.
_3	20041001	Product data sheet (9397 750 13728). Supersedes data of 2003 May 02 (9397 750 11464).
_2	20030502	Product data (9397 750 11464); ECN 853-2397 29856 Dated 24 April2003. Supersedes data of 2002 Dec 13 (9397 750 10859).
_1	20021213	Product data (9397 750 10859); ECN 853–2397 29264 of 09 December 2002.

## 4-bit I<sup>2</sup>C-bus LED driver with programmable blink rates

PCA9553

#### **Legal Information**

#### **Data sheet status**

Document status [1][2]	Product status <sup>[3]</sup>	Definition
Objective [short] data sheet	Development	This document contains data from the objective specification for product development.
Preliminary [short] data sheet	Qualification	This document contains data from the preliminary specification.
Product [short] data sheet	Production	This document contains the product specification.

- [1] Please consult the most recently issued document before initiating or completing a design.
- [2] The term 'short data sheet' is explained in section "Definitions".
- [3] The product status of device(s) described in this document may have changed since this data sheet was published and may differ in case of multiple devices. The latest product status information is available on the Internet at URL http://www.semiconductors.philips.com.

#### **Definitions**

Draft — The document is a draft version only. The content is still under internal review and subject to formal approval, which may result in modifications or additions. Philips Semiconductors does not give any representations or warranties as to the accuracy or completeness of information included herein and shall have no liability for the consequences of use of such information.

Short data sheet — A short data sheet is an extract from a full data sheet with the same product type number(s) and title. A short data sheet is intended for quick reference only and should not be relied upon to contain detailed and full information. For detailed and full information see the relevant full data sheet, which is available on request via the local Philips Semiconductors sales office. In case of any inconsistency or conflict with the short data sheet, the full data sheet shall prevail.

#### **Disclaimers**

**General** — Information in this document is believed to be accurate and reliable. However, Philips Semiconductors does not give any representations or warranties, expressed or implied, as to the accuracy or completeness of such information and shall have no liability for the consequences of use of such information.

Right to make changes — Philips Semiconductors reserves the right to make changes to information published in this document, including without limitation specifications and product descriptions, at any time and without notice. This document supersedes and replaces all information supplied prior to the publication hereof.

Suitability for use — Philips Semiconductors products are not designed, authorized or warranted to be suitable for use in medical, military, aircraft, space or life support equipment, nor in applications where failure or malfunction of a Philips Semiconductors product can reasonably be expected to result in personal injury, death or severe property or environmental damage. Philips Semiconductors accepts no liability for

inclusion and/or use of Philips Semiconductors products in such equipment or applications and therefore such inclusion and/or use is at the customer's own risk.

**Applications** — Applications that are described herein for any of these products are for illustrative purposes only. Philips Semiconductors makes no representation or warranty that such applications will be suitable for the specified use without further testing or modification.

Limiting values — Stress above one or more limiting values (as defined in the Absolute Maximum Ratings System of IEC 60134) may cause permanent damage to the device. Limiting values are stress ratings only and operation of the device at these or any other conditions above those given in the Characteristics sections of this document is not implied. Exposure to limiting values for extended periods may affect device reliability.

Terms and conditions of sale — Philips Semiconductors products are sold subject to the general terms and conditions of commercial sale, as published at <a href="http://www.semiconductors.philips.com/profile/terms">http://www.semiconductors.philips.com/profile/terms</a>, including those pertaining to warranty, intellectual property rights infringement and limitation of liability, unless explicitly otherwise agreed to in writing by Philips Semiconductors. In case of any inconsistency or conflict between information in this document and such terms and conditions, the latter will prevail

**No offer to sell or license** — Nothing in this document may be interpreted or construed as an offer to sell products that is open for acceptance or the grant, conveyance or implication of any license under any copyrights, patents or other industrial or intellectual property rights.

#### **Trademarks**

Notice: All referenced brands, product names, service names and trademarks are the property of their respective owners.

 ${\it l^2C ext{-}bus}$  — logo is a trademark of Koninklijke Philips Electronics N.V.

#### Contact information

For additional information please visit: http://www.semiconductors.philips.com

For sales office addresses, send an e-mail to: sales.addresses@www.semiconductors.philips.com



Please be aware that important notices concerning this document and the product(s) described herein, have been included in section 'Legal information'.

© Koninklijke Philips Electronics N.V. 2006. All rights reserved. For more information, please visit http://www.semiconductors.philips.com. For sales office addresses, email to: sales.addresses@www.semiconductors.philips.com.

Date of release: 20060818

Document identifier: PCA9553 4