## INTEGRATED CIRCUITS

# DATA SHEET

# XA-S3

XA 16-bit microcontroller
32 K/1 K OTP/ROM/ROMless, 8-channel 8-bit A/D, low voltage (2.7 V–5.5 V), I<sup>2</sup>C, 2 UARTs, 16 MB address range

Preliminary specification Supersedes data of 2000 Aug 22 2000 Dec 01





XA 16-bit microcontroller 32 K/1 K OTP/ROM/ROMless, 8-channel 8-bit A/D, low voltage (2.7 V–5.5 V), I<sup>2</sup>C, 2 UARTs, 16 MB address range

XA-S3

#### GENERAL DESCRIPTION

The XA-S3 device is a member of Philips Semiconductors' XA (eXtended Architecture) family of high performance 16-bit single-chip microcontrollers.

The XA-S3 device combines many powerful peripherals on one chip. With its high performance A/D converter, timers/counters, watchdog, Programmable Counter Array (PCA), I<sup>2</sup>C interface, dual UARTs, and multiple general purpose I/O ports, it is suited for general multipurpose high performance embedded control functions.

#### Specific features of the XA-S3

- 2.7 V to 5.5 V operation.
- 32 K bytes of on-chip EPROM/ROM program memory.
- 1024 bytes of on-chip data RAM.
- Supports off-chip addressing up to 16 megabytes (24 address lines). A clock output reference is added to simplify external bus interfacing.
- High performance 8-channel 8-bit A/D converter with automatic channel scan and repeated read functions. Completes a conversion in 4.46 microseconds at 30 MHz. Alternate operating mode allows 10-bit conversion results.

- Three standard counter/timers with enhanced features. All timers have a toggle output capability.
- Watchdog timer.
- 5-channel 16-bit Programmable Counter Array (PCA).
- I<sup>2</sup>C-bus serial I/O port with byte-oriented master and slave functions.
- Two enhanced UARTs with independent baud rates.
- Seven software interrupts.
- Active low reset output pin indicates all reset occurrences (external reset, watchdog reset and the RESET instruction). A reset source register allows program determination of the cause of the most recent reset.
- 50 I/O pins, each with 4 programmable output configurations.
- 30 MHz operating frequency at 2.7-5.5 V V<sub>DD</sub>.
- Power saving operating modes: Idle and Power-down. Wake-up from power-down via an external interrupt is supported.
- 68-pin PLCC and 80-pin PQFP packages.

#### ORDERING INFORMATION

ROMIess	ROM	EPROM		TEMPERATURE RANGE (°C) AND PACKAGE	FREQ. (MHz)	DRAWING NUMBER
PXAS30KBA	PXAS33KBA	PXAS37KBA	OTP	0 to +70, Commercial 68-pin Plastic Leaded Chip Carrier	30	SOT188-3
PXAS30KBBE	PXAS33KBBE	PXAS37KBBE	OTP	0 to +70, Commercial 80-pin Plastic Low Profile Quad Flat Pack	30	SOT315-1
PXAS30KFA	PXAS33KFA	PXAS37KFA	OTP	–40°C to +85°C, Industrial 68-pin Plastic Leaded Chip Carrier	30	SOT188-3
PXAS30KFBE	PXAS33KFBE	PXAS37KFBE	OTP	-40°C to +85°C, Industrial 80-pin Plastic Low Profile Quad Flat Pack	30	SOT315-1


2000 Dec 01 2

Downloaded from Elcodis.com electronic components distributor

XA-S3


#### **PIN CONFIGURATIONS**

## 68-pin PLCC package



XA-S3


## 80-pin LQFP package



2000 Dec 01


XA-S3

## **LOGIC SYMBOL**



XA-S3

## **BLOCK DIAGRAM**



2000 Dec 01

6

XA-S3

## **PIN DESCRIPTIONS**

	PIN NU	IMBER		
MNEMONIC	PLCC	LQFP	TYPE	NAME AND FUNCTION
V <sub>SS</sub>	1, 20, 55	12, 13, 53, 54, 69, 70	I	Ground: 0 V reference.
V <sub>DD</sub>	2, 21, 54	14, 15, 51, 52, 71, 72	I	Power Supply: This is the power supply voltage for normal, idle, and power down operation.
RST	50	47	I	<b>Reset:</b> A low on this pin resets the microcontroller, causing I/O ports and peripherals to take on their default states, and the processor to begin execution at the address contained in the reset vector.
RSTOUT	19	11	0	<b>Reset Output:</b> This pin outputs a low whenever the XA-S3 processor is reset for any reason. This includes an external reset via the $\overline{\text{RST}}$ pin, watchdog reset, and the $\overline{\text{RESET}}$ instruction.
ALE/PROG	47	44	I/O	Address Latch Enable/Program Pulse: A high output on the ALE pin signals external circuitry to latch the address portion of the multiplexed address/data bus. A pulse on ALE occurs only when it is needed in order to process a bus cycle.
PSEN	48	45	0	Program Store Enable: The read strobe for external program memory. When the microcontroller accesses external program memory, PSEN is driven low in order to enable memory devices. PSEN is only active when external code accesses are performed.
EA/WAIT/V <sub>PP</sub>	22	16	ı	External Access/Bus Wait: The $\overline{\text{EA}}$ input determines whether the internal program memory of the microcontroller is used for code execution. The value on the $\overline{\text{EA}}$ pin is latched as the external reset input is released and applies during later execution. When latched as a 0, external program memory is used exclusively. When latched as a 1, internal program memory will be used up to its limit, and external program memory used above that point. After reset is released, this pin takes on the function of bus WAIT input. If WAIT is asserted high during an external bus access, that cycle will be extended until WAIT is released.
XTAL1	68	68	Ι	Crystal 1: Input to the inverting amplifier used in the oscillator circuit and input to the internal clock generator circuits.
XTAL2	67	67	I	Crystal 2: Output from the oscillator amplifier.
CLKOUT	49	46	0	Clock Output: This pin outputs a buffered version of the internal CPU clock. The clock output may be used in conjunction with the external bus to synchronize WAIT state generators, etc. The clock output may be disabled by software.
$AV_{DD}$	33	28, 29	I	Analog Power Supply: Positive power supply input for the A/D converter.
AV <sub>SS</sub>	34	30, 31	I	Analog Ground.
AV <sub>REF+</sub>	32	27	I	A/D Positive Reference Voltage: High end reference for the A/D converter.
AV <sub>REF</sub>	31	26	I	A/D Negative Reference Voltage: Low end reference for the A/D converter.
P0.0 – P0.7	45, 46, 51–53, 56–58	42, 43, 48–50, 55–57	I/O	Port 0: Port 0 is an 8-bit I/O port with a user-configurable output type. Port 0 latches have 1s written to them and are configured in the quasi-bidirectional mode during reset. The operation of port 0 pins as inputs and outputs depends upon the port configuration selected. Each port pin is configured independently. Refer to the section on I/O port configuration and the DC Electrical Characteristics for details.
				When the external program/data bus is used, Port 0 becomes the multiplexed low data/instruction byte and address lines 4 through 11.

	PIN NU	JMBER			
MNEMONIC	PLCC	LQFP	TYPE		NAME AND FUNCTION
P1.0 – P1.7	35–42	32–39	I/O	1s written to them and ar operation of port 1 pins a selected. Each port pin is	I/O port with a user-configurable output type. Port 1 latches have e configured in the quasi-bidirectional mode during reset. The is inputs and outputs depends upon the port configuration configured independently. Refer to the section on I/O port Electrical Characteristics for details.
			l	Port 1 also provides vario	ous special functions as described below:
	35	32	0	A0/WRH (P1.0)	Address bit 0 of the external address bus when the eternal data bus is configured for an 8-bit width. When the external data bus is configured for a 16-bit width, this pin becomes the high byte write strobe.
	36	33	0	A1 (P1.1):	Address bit 1 of the external address bus.
	37	34	0	A2 (P1.2):	Address bit 2 of the external address bus.
	38	35	0	A3 (P1.3):	Address bit 3 of the external address bus.
	39	36	1	RxD1 (P1.4):	Serial port 1 receiver input.
	40	37	0	TxD1 (P1.5):	Serial port 1 transmitter output.
	41	38	I/O	T2 (P1.6):	Timer/counter 2 external count input or overflow output.
	42	39	0	T2EX (P1.7):	Timer/counter 2 reload/capture/direction control.
P2.0 – P2.7	59–66	58, 59, 61–66	I/O	1s written to them and ar operation of port 2 pins a selected. Each port pin is	I/O port with a user-configurable output type. Port 2 latches have re configured in the quasi-bidirectional mode during reset. The is inputs and outputs depends upon the port configuration configured independently. Refer to the section on I/O port Electrical Characteristics for details.
				multiplexed high data/ins	am/data bus is used in 16-bit mode, Port 2 becomes the struction byte and address lines 12 through 19. When the external d in 8-bit mode, the number of address lines that appear on Port 2 groups of 4 bits.
P3.0 – P3.7	11–18	3–10	I/O	1s written to them and ar operation of port 3 pins a selected. Each port pin is	I/O port with a user-configurable output type. Port 3 latches have e configured in the quasi-bidirectional mode during reset. The is inputs and outputs depends upon the port configuration configured independently. Refer to the section on I/O port Electrical Characteristics for details.
				Port 3 also provides the	various special functions as described below:
	11	3	1	RxD0 (P3.0):	Receiver input for serial port 0.
	12	4	0	TxD0 (P3.1):	Transmitter output for serial port 0.
	13	5	1	ĪNT0 (P3.2):	External interrupt 0 input.
	14	6	1	ĪNT1 (P3.3):	External interrupt 1 input.
	15	7	I/O	T0 (P3.4):	Timer/counter 0 external count input or overflow output.
	16	8	I/O	T1 / BUSW (P3.5):	Timer/counter 1 external count input or overflow output. The value on this pin is latched as an external chip reset is completed and defines the default external data bus width.
	17	9	0	WRL (P3.6):	External data memory low byte write strobe.
	18	10	0	RD (P3.7):	External data memory read strobe.
P4.0 – P4.7	3–10	73–79, 2	I/O	1s written to them and ar operation of Port 4 pins a selected. Each port pin is configuration and the DC	I/O port with a user-configurable output type. Port 4 latches have be configured in the quasi-bidirectional mode during reset. The as inputs and outputs depends upon the port configuration is configured independently. Refer to the section on I/O port is Electrical Characteristics for details.
				· '	ous special functions as described below:
	3	73	'	ECI (P4.0):	PCA External clock input.
	4	74	I/O	CEX0 (P4.1):	Capture/compare external I/O for PCA module 0.
	5	75	I/O	CEX1 (P4.2):	Capture/compare external I/O for PCA module 1.
	6	76	I/O	CEX2 (P4.3):	Capture/compare external I/O for PCA module 2.
	7	77	I/O	CEX3 (P4.4):	Capture/compare external I/O for PCA module 3.
	8	78	I/O	CEX4 (P4.5):	Capture/compare external I/O for PCA module 4.
	9	79	0	A20 (P4.6):	Address bit 20 of the external address bus.
	10	2	0	A21 (P4.7):	Address bit 21 of the external address bus.

8

2000 Dec 01

XA-S3

MNEMONIC	PIN NU	IMBER	TYPE		NAME AND FUNCTION		
WINEWIONIC	PLCC	LQFP	ITPE		NAME AND FUNCTION		
P5.0 – P5.7	23–30	17–20, 22–25	I/O	<b>Port 5:</b> Port 5 is an 8-bit I/O port with a user-configurable output type. Port 5 latches have 1s written to them and are configured in the quasi-bidirectional mode during reset. The operation of Port 5 pins as inputs and outputs depends upon the port configuration selected. Each port pin is configured independently. Refer to the section on I/O port configuration and the DC Electrical Characteristics for details.			
				Port 5 also provides various special functions as described below. Port 5 pins used as A/l inputs must be configured by the user to the high impedance mode.			
	23	17	I	AD0 (P5.0):	A/D channel 0 input.		
	24	18	I	AD1 (P5.1):	A/D channel 1 input.		
	25	19	I	AD2 (P5.2):	A/D channel 2 input.		
	26	20	I	AD3 (P5.3):	A/D channel 3 input.		
	27	22	I	AD4 (P5.4):	A/D channel 4 input.		
	28	23	I	AD5 (P5.5):	A/D channel 5 input.		
	29	24	I/O	AD6/SCL (P5.6):	A/D channel 6 input. I <sup>2</sup> C serial clock input/output.		
	30	25	I/O	AD7/SDA (P5.7):	A/D channel 7 input. I <sup>2</sup> C serial data input/output.		
P6.0 – P6.7	43, 44	40, 41	I/O	Port 6: Port 6 is a 2-bit I/O port with a user-configurable output type. Port 6 latches have 1s written to them and are configured in the quasi-bidirectional mode during reset. The operation of Port 6 pins as inputs and outputs depends upon the port configuration selected. Each port pin is configured independently. Refer to the section on I/O port configuration and the DC Electrical Characteristics for details.			
				Port 6 also provides special functions as described below:			
	43	40	0	A22 (P6.0): Address bit 22 of the external address bus.			
	44	41	0	A23 (P6.1):	Address bit 23 of the external address bus.		

**Table 1. Special Function Registers** 

		SFR			BIT FUNC	CTIONS A	ND ADDI	RESSES			Reset
NAME	DESCRIPTION	Address	MSB							LSB	Value
			3F7	3F6	3F5	3F4	3F3	3F2	3F1	3F0	
ADCON#*	A/D control register	43E	_	_	_	_	ADRES	ADMOD	ADSST	ADINT	00h
			3FF	3FE	3FD	3FC	3FB	3FA	3F9	3F8	1
ADCS#*	A/D channel select register	43F	ADCS7	ADCS6	ADCS5	ADCS4	ADCS3	ADCS2	ADCS1	ADCS0	00h
ADCFG#	A/D timing configuration	4B9	-	_	-	-	A/I	D Timing (	Configurat	ion	0Fh
ADRSH0#	A/D high byte result, channel 0	4B0									xx
ADRSH1#	A/D high byte result, channel 1	4B1									xx
ADRSH2#	A/D high byte result, channel 2	4B2									xx
ADRSH3#	A/D high byte result, channel 3	4B3									xx
ADRSH4#	A/D high byte result, channel 4	4B4									xx
ADRSH5#	A/D high byte result, channel 5	4B5									xx
ADRSH6#	A/D high byte result, channel 6	4B6									xx
ADRSH7#	A/D high byte result, channel 7	4B7									xx
ADRSL#	Two LSBs of 10-bit A/D result	4B8									xx
BCR#	Bus configuration register	46A	-	_	CLKD	WAITD	BUSD	BC2	BC1	BC0	Note 1
BTRH	Bus timing register high byte	469	DW1	DW0	DWA1	DWA0	DR1	DR0	DRA1	DRA0	FFh
BTRL	Bus timing register low byte	468	WM1	WM0	ALEW	-	CR1	CR0	CRA1	CRA0	EFh
			2D7	2D6	2D5	2D4	2D3	2D2	2D1	2D0	1
CCON#*	PCA counter control	41A	CF	CR	_	CCF4	CCF3	CCF2	CCF1	CCF0	00h
CMOD#	PCA mode control	490	CIDL	WDTE	-	-	-	CPS1	CPS0	ECF	00h
CH#	PCA counter high byte	48B		•			•		•		00h
CL#	PCA counter low byte	48A									00h
CCAPM0#	PCA module 0 mode	491	-	ECOM0	CAPP0	CAPN0	MAT0	TOG0	PWM0	ECCF0	00h
CCAPM1#	PCA module 1 mode	492	-	ECOM1	CAPP1	CAPN1	MAT1	TOG1	PWM1	ECCF1	00h

2000 Dec 01

XA-S3

NAME	DESCRIPTION	SFR Address	MSB		BIT FUNC	CTIONS A	ND ADD	RESSES		LSB	Rese Value
CCAPM2#	PCA module 2 mode	493	-	ECOM2	CAPP2	CAPN2	MAT2	TOG2	PWM2	ECCF2	00h
CCAPM3#	PCA module 3 mode	494	_	ECOM3	CAPP3	CAPN3	MAT3	TOG3	PWM3	ECCF3	00h
CCAPM4#	PCA module 4 mode	495	_	ECOM4	CAPP4	CAPN4	MAT4	TOG4	PWM4	ECCF4	00h
CCAP0H#	PCA module 0 capture high byte	497									xx
CCAP1H#	PCA module 1 capture high byte	499									XX
CCAP2H#	PCA module 2 capture high byte	49B									xx
CCAP3H#	PCA module 3 capture high byte	49D									xx
CCAP4H#	PCA module 4 capture high byte	49F									xx
CCAP0L#	PCA module 0 capture low byte	496									xx
CCAP1L#	PCA module 1 capture low byte	498									xx
CCAP2L#	PCA module 2 capture low byte	49A									XX
CCAP3L#	PCA module 3 capture low byte	49C									XX
CCAP4L#	PCA module 4 capture low byte	49E									XX
CS DS	Code segment Data segment	443 441									00h 00h
ES	Extra segment	441									00h
LO	Extra segment	442	267	266	265	264	262	262	261	360	0011
120001#*	12C control register	420	367 CR2	366 ENA	365 STA	364 STO	363 SI	362 AA	361 CR1		00h
I2CON#*	I <sup>2</sup> C control register	42C	CRZ				51	_		CR0	4
I2STAT#	I <sup>2</sup> C status register	46C		I <sup>2</sup> C Sta	tus Code/	vector		0	0	0	F8h
I2DAT#	I <sup>2</sup> C data register	46D							XX		
I2ADDR#	I <sup>2</sup> C address register	46E				Slave Addı				GC	00h
			33F	33E	33D	33C	33B	33A	339	338	
IEH*	Interrupt enable high byte	427	-	_	_	_	ETI1	ERI1	ETI0	ERI0	00h
			337	336	335	334	333	332	331	330	
IEL#*	Interrupt enable low byte	426	EA	EAD	EPC	ET2	ET1	EX1	ET0	EX0	00h
			377	376	375	374	373	372	371	370	4
IELB#*	Interrupt enable B low byte	42E	_	_	El2	EC4	EC3	EC2	EC1	EC0	00h
IPA0	Interrupt priority A0	4A0	-		PT0		-		PX0		00h
IPA1	Interrupt priority A1	4A1	_		PT1				PX1		00h
IPA2#	Interrupt priority A2	4A2	-		PPC		_		PT2		00h
IPA3#	Interrupt priority A3	4A3	-		-		-		PAD		00h
IPA4	Interrupt priority A4	4A4	-		PTI0		_		PRI0		00h
IPA5	Interrupt priority A5	4A5	-		PTI1		_		PRI1		00h
IPB0#	Interrupt priority B0	4A8	-		PC1		_		PC0		00h
IPB1#	Interrupt priority B1	4A9	_		PC3		_		PC2		00h
IPB2#	Interrupt priority B2	4AA	_		PI2		_		PC4		00h
	, , ,		387	386	385	384	383	382	381	380	1
P0*	Port 0	430	A11D7	A10D6	A9D5	A8D4	A7D3	A6D2	A5D1	A4D0	FFh
. 0		400	38F	38E	38D	38C	38B	38A	389	388	<del> </del>
D1*	Dort 1	424		72						A0/WRH	
P1*	Port 1	431	T2EX		TxD1	RxD1	A3	A2	A1		FFh
<b>D</b> 04			397	396	395	394	393	392	391	390	
P2*	Port 2	432	A19D15	A18D14	A17D13	A16D12	A15D11	A14D10	A13D9	A12D8	FFh
			39F	39E	39D	39C	39B	39A	399	398	1
P3*	Port 3	433	RD	WRL	T1	T0	INT1	INT0	TxD0	RxD0	FFh
			3A7	3A6	3A5	3A4	3A3	3A2	3A1	3A0	
P4#*	Port 4	434	A21	A20	CEX4	CEX3	CEX2	CEX1	CEX0	ECI	FFh

XA-S3

NAME	DESCRIPTION	SFR Address	MSB		BIT FUNC	CTIONS A	ND ADD	RESSES		LSB	Res Val
			3AF	3AE	3AD	3AC	3AB	3AA	3A9	3A8	$\vdash$
P5#*	Port 5	435	AD7/SDA	AD6/SCL	AD5	AD4	AD3	AD2	AD1	AD0	┫ FFh
									3B1	3B0	1
P6#*	Port 6	436	<u> </u>				T _	Π_	A23	A22	$\left  \right _{FFr}$
0#	T OIL O	430							AZS	AZZ	┨'''
P0CFGA	Port 0 configuration A	470									Not
P1CFGA	Port 1 configuration A	471									Not
P2CFGA	Port 2 configuration A	472									Not
P3CFGA	Port 3 configuration A	473									Not
P4CFGA#	Port 4 configuration A	474									Not
P5CFGA#	Port 5 configuration A	475									Not
P6CFGA#	Port 6 configuration A	476	<del></del>			<del></del>		<del> </del>	<del>                                     </del>	<del>                                     </del>	Not
P0CFGB	Port 0 configuration B	4F0				<del>                                     </del>		<del>                                     </del>	<del>                                     </del>	<del>                                     </del>	Not
P1CFGB	Port 1 configuration B	4F1				<del>                                     </del>	Not				
P2CFGB	Port 2 configuration B	4F2				<del>                                     </del>	Not				
P3CFGB	Port 3 configuration B	4F3				<del>                                     </del>	Not				
P4CFGB#	Port 4 configuration B	4F4									Not
P5CFGB#	Port 5 configuration B	4F5	<u> </u>			<del> </del>	<del> </del>	<del> </del>	<del> </del>	-	Not
P6CFGB#	ľ	4F6									Not
POUFGB#	Port 6 configuration B	450	- 007						204	220	INOI
DOON!*	Danier and an eleter	40.4	227	226	225	224	223	222	221	220	-
PCON*	Power control register	404	-	-	-	-	-	-	PD	IDL	00h
DOIA!! !*		404	20F	20E	20D	20C	20B	20A	209	208	┨
PSWH*	Program status word (high byte)	401	SM	TM	RS1	RS0	IM3	IM2	IM1	IM0	Not
DOI: #			207	206	205	204	203	202	201	200	┨
PSWL*	Program status word (low byte)	400	C	AC	-			V	N	Z	Not
D011/-14			217	216	215	214	213	212	211	210	┨
PSW51*	80C51 compatible PSW	402	С	AC	F0	RS1	RS0	V	F1	Р	Not
RSTSRC#	Reset source register	463	_	_	_	_	_	R_WD	R_CMD	R_EXT	Not
RTH0	Timer 0 reload register, high byte	455									00h
RTH1	Timer 1 reload register, high byte	457									00h
RTL0	Timer 0 reload register, low byte	454									00h
RTL1	Timer 1 reload register, low byte	456									00h
			307	306	305	304	303	302	301	300	-
S0CON*	Serial port 0 control register	420	SM0_0	SM1_0	SM2_0	REN_0	TB8_0	RB8_0	TI_0	RI_0	00h
			30F	30E	30D	30C	30B	30A	309	308	-
S0STAT#*	Serial port 0 extended status	421		_	_	ERR0	FE0	BR0	OE0	STINT0	00h
S0BUF	Serial port 0 data buffer register	460 461									XX
S0ADDR S0ADEN	Serial port 0 address register Serial port 0 address enable	461 462									00h 00h
CONDEN	Sonai port o addicos citable	102	327	326	325	324	323	322	321	320	
S1CON*	Serial port 1 control register	424	SM0_1	SM1_1	SM2_1	REN_1	TB8_1	RB8_1	TI_1	RI_1	00H
			32F	32E	32D	32C	32B	32A	329	328	1 "
S1STAT#*	Serial port 1 extended status	425	- -	- JZL	-    -	ERR1	FE1	BR1	OE1	STINT1	- 00h
S1BUF	Serial port 1 data buffer register	464				ERRE		DIX.			XX
S1ADDR	Serial port 1 address register	465									00h

XA-S3

NAME	DESCRIPTION	SFR Address	MSB		BIT FUNC	CTIONS A	ND ADD	RESSES		LSB	Reset Value
S1ADEN	Serial port 1 address enable	466									00h
SCR	System configuration register	440	-	-	_	-	PT1	PT0	СМ	PZ	00h
			21F	21E	21D	21C	21B	21A	219	218	1
SSEL*	Segment selection register	403	ESWEN	R6SEG	R5SEG	R4SEG	R3SEG	R2SEG	R1SEG	R0SEG	00h
SWE	Software interrupt enable	47A	_	SWE7	SWE6	SWE5	SWE4	SWE3	SWE2	SWE1	00h
			357	356	355	354	353	352	351	350	1
SWR*	Software interrupt request	42A	-	SWR7	SWR6	SWR5	SWR4	SWR3	SWR2	SWR1	00h
			2C7	2C6	2C5	2C4	2C3	2C2	2C1	2C0	1
T2CON*	Timer 2 control register	418	TF2	EXF2	RCLK0	TCLK0	EXEN2	TR2	C/T2	CP/RL2	00h
			2CF	2CE	2CD	2CC	2CB	2CA	2C9	2C8	1
T2MOD*	Timer 2 mode control	419	-	_	RCLK1	TCLK1	_	-	T2OE	DCEN	00h
TH2 TL2 T2CAPH T2CAPL	Timer 2 high byte Timer 2 low byte Timer 2 capture, high byte Timer 2 capture, low byte	459 458 45B 45A									00h 00h 00h 00h
			287	286	285	284	283	282	281	280	
TCON*	Timer 0 and 1 control register	410	TF1	TR1	TF0	TR0	IE1	IT1	IE0	IT0	00h
TH0 TH1 TL0 TL1	Timer 0 high byte Timer 1 high byte Timer 0 low byte Timer 1 low byte	451 453 450 452									00h 00h 00h 00h
TMOD	Timer 0 and 1 mode control	45C	GATE	C/T	M1	M0	GATE	C/T	M1	M0	00h
			28F	28E	28D	28C	28B	28A	289	288	
TSTAT*	Timer 0 and 1 extended status	411	_	-	_	_	_	T10E	_	T0OE	00h
			2FF	2FE	2FD	2FC	2FB	2FA	2F9	2F8	]
WDCON*	Watchdog control register	41F	PEW2	PRE1	PRE0	_	_	WDRUN	WDTOF	_	Note 6
WDL WFEED1 WFEED2	Watchdog timer reload Watchdog feed 1 Watchdog feed 2	45F 45D 45E									00h xx xx

#### NOTES:

- \* SFRs are bit addressable.
- # SFRs are modified from or added to XA-G3 SFRs.
- 1. At reset, the BCR is loaded with the binary value 00000a11, where "a' is the value on the BUSW pin. This defaults the address bus size to 24 bits.
- 2. SFR is loaded from the reset vector.
- 3. All bits except F1, F0, and P are loaded from the reset vector. Those bits are all 0.
- 4. Unimplemented bits in SFRs are X (unknown) at all times. Ones should not be written to these bits since they may be used for other purposes in future XA derivatives. The reset value shown for these bits is 0.
- 5. Port configurations default to quasi-bidirectional when the XA begins execution from internal code memory after reset, based on the condition found on the EA pin. Thus, all PnCFGA registers will contain FF, and PnCFGB register will contain 00 when the XA begins execution using internal code memory. When the XA begins execution using external code memory, the default configuration for pins that are associated with the external bus will be push-pull. The PnCFGA and PnCFGB register contents will reflect this difference.
- 6. The WDCON reset value is E6 for a Watchdog reset, E4 for all other reset causes.
- 7. The RSTSRC register reflects the cause of the last XA-S3 reset. One bit will be set to 1, the others will be cleared to 0.
- 8. The XA guards writes to certain bits (typically interrupt flags) that may be altered directly by a peripheral function. This prevents loss of an interrupt or other status if a bit was written directly by a peripheral action during the time between the read and write portions of an instruction that performs a read-modify-write operation. Examples of such instructions are:

and s0con,#\$fb
clr tr0
setb ti\_0

XA-S3 SFR bits that are guarded in this manner are: ADINT (in ADCON); CF, CCF4, CCF3, CCF2, CCF1, and CCF0 (in CCON); SI (in I2CON); TI\_0 and RI\_0 (in S0CON); TI\_1 and RI\_1 (in S1CON); FE0, BR0, and OE0 (in S0STAT); FE1, BR1, and OE1 (in S1STAT); TF2 (in T2CON); TF1, TF0, IE1, and IE0 (in TCON); and WDTOF (in WDCON).

9. The XA-S3 implements an 8-bit SFR bus, as stated in *Chapter 8* of the *XA User Guide*. All SFR accesses must be 8-bit operations. Attempts to write 16 bits to an SFR will actually write only the lower 8 bits. Sixteen bit SFR reads will return undefined data in the upper byte.




Figure 1. XA-S3 program memory map




Figure 2. XA-S3 data memory map

XA-S3

#### **FUNCTIONAL DESCRIPTION**

Details of XA-S3 functions will be described in the following sections.

#### Analog to Digital converter

The XA-S3 has an 8-channel, 8-bit A/D converter with 8 sets of result registers, single scan and multiple scan operating modes. The A/D also has a 10-bit conversion mode that provides greater result resolution. The A/D input range is limited to 0 to AV<sub>DD</sub> (3.3 V max.). The A/D inputs are on Port 5. Analog Power and Ground as well as AV<sub>REF+</sub> and AV<sub>REF-</sub> must be supplied in order for the A/D converter to be used. Prior to enabling the A/D converter or driving analog signals into the A/D inputs, the port configurations for the pins being used as A/D inputs must be set to the "off" (high impedance, input only) mode.

A/D timing can be adapted to the application clock frequency in order to provide the fastest possible conversion.

A/D converter operation is controlled through the ADCON (A/D Control) register, see Figure 1. Bits in ADCON start and stop the A/D, flag conversion completion, and select the converter operating modes. When 10-bit resolution is needed, the A/D mode may be set to give 10 result bits by setting the ADRES bit to 1. In this mode, the A/D takes longer to complete a conversion, and the timing must be set differently in ADCFG.

#### A/D Conversion Modes

The A/D converter supports a single scan mode and a continuous scan mode. In either mode, one or more A/D channels may be converted. The ADCS register determines which channels are converted. If the corresponding bit in the ADCS register is set, that channel is selected for conversions, otherwise that channel is skipped. The ADCS register is detailed in Figure 2.

For any A/D conversion, the results are stored in ADRSHn, corresponding to the A/D channel just converted. For a 10-bit conversion, the two least significant bits are read from the upper end

of register ADRSL. These bits must be read before another conversion is begun.

A/D conversions are begun by setting the A/D Start and STatus bit in ADCON. In the single scan mode, all of the channels selected by bits in the ADCS register will be converted once. The ADINT flag is set when the last channel is converted. In the continuous scan mode, the A/D converter continuously converts all A/D channels selected by bits in the ADCS register. The ADINT flag is set when all channels have been converted once.

The A/D converter can generate an interrupt when the ADINT flag is set. This will occur if the A/D interrupt is enabled (via the EAD bit in IEL), the interrupt system is enabled (via the EA bit in IEL), and the A/D interrupt priority (specified in IPA3 bits 3 to 0) is higher than the currently running code (PSW bits IM3 through IM0) and any other pending interrupt. ADINT must be cleared by software.

#### A/D Timing Configuration

The A/D sampling and conversion timing may be optimized for the particular oscillator frequency and input drive characteristics of the application. Because A/D operation is mostly dependent on real-time effects (charging time of sampling capacitors, settling time of the comparator, etc.), A/D conversion times are not necessarily much longer at slower clock frequencies. The A/D timing is controlled by the ADCFG register, as shown in Figure 3, Table 2 and Table 3.

The primary effect of ADCFG settings is to adjust the A/D sample and hold time to be relatively constant over various clock frequencies. Two settings (value 6 and B) are provided to allow fast conversions with a lower external source driving the A/D inputs. These settings provide double the sample time at the same frequency. Of course, settings intended for lower frequencies may also be used at higher frequencies in order to increase the A/D sampling time, but this method has the side effect of significantly increasing A/D conversion times.

ADCON Address Bit Addressable Reset Value: 00h	ss:43Eh	MSB         LSB           —         —         ADRES ADMOD ADSST ADINT						
BIT	SYMBOL	FUNCTION						
ADCON.7	_	Reserved for future use. Should not be set to 1 by user programs.						
ADCON.6	_	Reserved for future use. Should not be set to 1 by user programs.						
ADCON.5	_	Reserved for future use. Should not be set to 1 by user programs.						
ADCON.4	_	Reserved for future use. Should not be set to 1 by user programs.						
ADCON.3	ADRES	Selects 8-bit (0) or 10-bit (1) conversion mode.						
ADCON.2	ADMOD	A/D mode select.  1 = continuous scan of selected inputs after a start of the A/D.  0 = single scan of selected inputs after a start of the A/D.						
ADCON.1	ADSST	A/D start and status. Setting this bit by software starts the A/D conversion of the selected A/D inputs. ADSST remains set as long as the A/D is in operation. In continuous conversion mode, ADSST will remain set unless the A/D is stopped by software. While ADSST is set, new start commands are ignored. An A/D conversion is progress may be aborted by software clearing ADSST.						
ADCON.0	ADINT	A/D conversion complete/interrupt flag. This flag is set when all selected A/D channels are converted in either the single scan or continuous scan modes. Must be cleared by software.						
		SU01229						

Figure 1. A/D Control Register (ADCON)

XA-S3




Figure 2. A/D Channel Select Register (ADCS)

ADCFG Address:	4B9h	MSB LSB
Not bit Addressable Reset Value: 00h		— — — A/D Timing Configuration
віт	SYMBOL	FUNCTION
ADCFG.7	_	Reserved for future use. Should not be set to 1 by user programs.
ADCFG.6	_	Reserved for future use. Should not be set to 1 by user programs.
ADCFG.5	_	Reserved for future use. Should not be set to 1 by user programs.
ADCFG.4	_	Reserved for future use. Should not be set to 1 by user programs.
ADCFG.3-0	ADCFG	A/D timing configuration (see text and table).
		SU00940

Figure 3. A/D Timing Configuration Register (ADCFG)

Table 2. A/D Timing Configuration

ADOFO 2 A	Max. Oscillator	Conv	ersion Time	Sampling Time
ADCFG.3-0	Frequency (MHz)	Osc. Clocks	μ <b>sec at max. Osc.</b>	(Osc. Clocks)
0h (0000)	6.66	72	10.81	4
1h (0001)	10	76	7.6	6
2h (0010)	11.11	80	7.2	8
3h (0011)	13.33	96	7.2	8
4h (0100)	16.66	100	6.0	10
5h (0101)	20	104	5.2	12
6h (0110) <sup>1</sup>	20	116	5.8	24
7h (0111)	22.2	108	4.86	14
8h (1000)	23.3	124	5.32	14
9h (1001)	26.6	128	4.81	16
Ah (1010)	30	132	4.4	18
Bh (1011) <sup>1</sup>	30	146	4.87	32
Ch (1100)	-	136	4.25	20
Dh (1101)	-	152	4.56	20
Eh (1110)	-	172	4.7	22
Fh (1111)	-	176	4.4	24

#### NOTE:

<sup>1.</sup> These settings provide additional A/D input sampling time, in order to allow accurate readings with a higher external source impedance.

XA-S3

Table 3. A/D Timing Configuration for 10-bit Mode

45050.0.0	Max. Oscillator	Conv	ersion Time	Sampling Time
ADCFG.3-0	Frequency (MHz)	Osc. Clocks	μ <b>sec at max. Osc.</b>	(Osc. Clocks)
0h (0000)	6.66	88	13.21	4
1h (0001)	8	92	9.2	6
2h (0010)	8	96	8.64	8
3h (0011)	12	116	8.7	8
4h (0100)	12	120	7.2	10
5h (0101)	12	124	6.2	12
6h (0110)	12	136	6.8	24
7h (0111)	12	128	5.77	14
8h (1000)	13	148	6.35	14
9h (1001)	13	152	5.71	16
Ah (1010)	13	156	5.2	18
Bh (1011)	13	170	5.67	32
Ch (1100)	13	160	5.0	20
Dh (1101)	16	180	5.41	20
Eh (1110)	20	204	5.57	22
Fh (1111)	20	208	5.2	24

#### A/D Inputs

In order to obtain accurate measurements with the A/D Converter, the source drive must be sufficient to adequately charge the sampling capacitor during the sampling time. Figure 4 shows the equivalent resistance and capacitance related to the A/D inputs. A/D timing configurations indicated in Table 1 allow for full A/D

accuracy (according to the A/D specifications) assuming a source resistance of less than or equal to  $20k\Omega$ . Larger source resistances may be accommodated by increasing the sampling time with a different A/D timing configuration.




Figure 4. A/D Input: Equivalent Circuit

XA 16-bit microcontroller 32 K/1 K OTP/ROM/ROMless, 8-channel 8-bit A/D, low voltage (2.7 V–5.5 V), I<sup>2</sup>C, 2 UARTs, 16 MB address range

XA-S3

#### A/D Accuracy

The XA-S3 A/D in 10 -bit mode is specified with 16 samples averaged in order to factor out on-chip noise. In an application where averaging 16 samples is not practical, the accuracy specifications may be de-rated according to the number of samples

that are actually taken. The graph in Figure 5 shows the relationship of additional A/D error to the number of samples that are averaged. For example, if a single A/D reading is used with no averaging, the A/D accuracy should be de-rated by  $\pm 1.25$  LSB.




Figure 5. A/D accuracy by number of averaging samples (Pertains to 10-bit mode only. Note that 10-bit mode is only specified up to  $f_C = 20$  MHz.)

I2CON Addres	s:42Ch	MSB							LSB	
Bit Addressable Reset Value: 00h		CR2	ΞNΑ	STA	STO	SI	AA	CR1	CR0	
ВІТ	SYMBOL	FUNCTION								
I2CON.7	CR2	I <sup>2</sup> C Rate Con	trol, with	n CR1 an	d CR0. S	ee text an	d table.			
I2CON.6	ENA	Enable I <sup>2</sup> C po	ort. Whe	n ENA =	1, the $I^2C$	port is e	nabled.			
I2CON.5	STA	Start flag. Se generating a			uses the I	<sup>2</sup> C interfa	ce to atter	mpt to gai	n masters	hip of the bus by
I2CON.4	STO	Stop flag. Set	ting STC	O to 1 ca	uses the I	<sup>2</sup> C interfa	ce to atte	mpt to ger	nerate a S	top condition.
I2CON.3	SI	Serial Interru software nee								indicating that ent priority.
I2CON.2	AA	Assert Ackno acknowledge	wledge. pulses f	Setting <i>i</i> for variou	AA to 1 ca us conditio	uses the ons (see to	I <sup>2</sup> C hardw ext).	are to aut	tomatically	generate
I2CON.1	CR1	I <sup>2</sup> C Rate Con	trol, with	n CR2 an	d CR0. S	ee text an	d table.			
I2CON.0	CR0	I <sup>2</sup> C Rate Con	trol, with	n CR2 an	d CR1. S	ee text an	d table.			
										SU00941

Figure 6. I<sup>2</sup>C Control Register (I2CON)

2000 Dec 01 17

Downloaded from **Elcodis.com** electronic components distributor

XA 16-bit microcontroller 32 K/1 K OTP/ROM/ROMless, 8-channel 8-bit A/D, low voltage (2.7 V–5.5 V), I<sup>2</sup>C, 2 UARTs, 16 MB address range

XA-S3

#### I<sup>2</sup>C Interface

The I<sup>2</sup>C interface on the XA-S3 is identical to the standard byte-style I<sup>2</sup>C interface found on devices such as the 8xC552 except for the rate selection. The I<sup>2</sup>C interface conforms to the 100 kHz I<sup>2</sup>C specification, but may be used at rates up to 400 kHz (non-conforming).

**Important:** Before the I<sup>2</sup>C interface may be used, the port pins P5.6 and 5.7, which correspond to the I<sup>2</sup>C functions SCL and SDA respectively, must be set to the open drain mode.

The processor interfaces to the I<sup>2</sup>C logic via the following four special function registers: I2CON (I<sup>2</sup>C control register), I2STA (I<sup>2</sup>C status register), I2DAT (I<sup>2</sup>C data register), and I2ADR (I<sup>2</sup>C slave address register). The I<sup>2</sup>C control logic interfaces to the external I<sup>2</sup>C bus via two port 5 pins: P5.6/SCL (serial clock line) and P5.7/SDA (serial data line).

#### The Control Register, I2CON

This register is shown in Figure 6. Two bits are affected by the  $I^2C$  hardware: the SI bit is set when a serial interrupt is requested, and the STO bit is cleared when a STOP condition is present on the  $I^2C$  bus. The STO bit is also cleared when ENA = "0".

#### ENA, the I2C Enable Bit

**ENA = 0:** When ENA is "0", the SDA and SCL outputs are not driven. SDA and SCL input signals are ignored, SIO1 is in the "not addressed" slave state, and the STO bit in I2CON is forced to "0". No other bits are affected. P5.6 and P5.7 may be used as open drain I/O ports.

**ENA = 1:** When ENA is "1", SIO1 is enabled. The P5.6 and P5.7 port latches must be set to logic 1.

ENA should not be used to temporarily release the  $I^2$ C-bus since, when ENA is reset, the  $I^2$ C-bus status is lost. The AA flag should be used instead (see description of the AA flag in the following text).

In the following text, it is assumed the ENA = "1".

## STA, the START flag

**STA = 1:** When the STA bit is set to enter a master mode, the  $I^2C$  hardware checks the status of the  $I^2C$  bus and generates a START condition if the bus is free. If the bus is not free, the  $I^2C$  interface waits for a STOP condition (which will free the bus) and generates a START condition after a delay of a half clock period of the internal serial clock generator.

If STA is set while the  $I^2C$  interface is already in a master mode and one or more bytes are transmitted or received, the hardware transmits a repeated START condition. STA may be set at any time. STA may also be set when the  $I^2C$  interface is an addressed slave.

STA = 0: When the STA bit is reset, no START condition or repeated START condition will be generated.

#### STO, the STOP flag

**STO = 1:** When the STO bit is set while the  $I^2C$  interface is in a master mode, a STOP condition is transmitted to the  $I^2C$  bus. When the STOP condition is detected on the bus, the hardware clears the STO flag. In a slave mode, the STO flag may be set to recover from an error condition. In this case, no STOP condition is transmitted to the  $I^2C$  bus. However, the hardware behaves as if a STOP condition has been received and switches to the defined "not addressed" slave receiver mode. The STO flag is automatically cleared by hardware.

If the STA and STO bits are both set, then a STOP condition is transmitted to the  $I^2C$  bus if the interface is in a master mode (in a slave mode, the hardware generates an internal STOP condition which is not transmitted). The  $I^2C$  interface then transmits a START condition.

STO = 0: When the STO bit is reset, no STOP condition will be generated.

#### SI, the Serial Interrupt flag

SI = 1: When the SI flag is set, and the EA (interrupt system enable) and EI2 ( $I^2C$  interrupt enable) bits are also set, an  $I^2C$  interrupt is requested. SI is set by hardware when one of 25 of the 26 possible  $I^2C$  interface states is entered. The only state that does not cause SI to be set is state F8H, which indicates that no relevant state information is available.

While SI is set, the low period of the serial clock on the SCL line is stretched, and the serial transfer is suspended. A high level on the SCL line is unaffected by the serial interrupt flag. SI must be reset by software.

**SI = 0:** When the SI flag is reset, no serial interrupt is requested, and there is no stretching of the serial clock on the SCL line.

#### AA, the Assert Acknowledge flag

**AA = 1:** If the AA flag is set, an acknowledge (low level to SDA) will be returned during the acknowledge clock pulse on the SCL line when:

- The "own slave address" has been received.
- The general call address has been received while the general call bit (GC) in I2ADR is set.
- A data byte has been received while the I<sup>2</sup>C interface is in the master receiver mode.
- A data byte has been received while the I<sup>2</sup>C interface is in the addressed slave receiver mode.

**AA = 0:** If the AA flag is reset, a not acknowledge (high level to SDA) will be returned during the acknowledge clock pulse on the SCL line when:

- A data byte has been received while the I<sup>2</sup>C interface is in the master receiver mode.
- A data byte has been received while the I<sup>2</sup>C interface is in the addressed slave receiver mode.

When the  $I^2C$  interface is in the addressed slave transmitter mode, state C8H will be entered after the last serial data byte is transmitted. When SI is cleared, the  $I^2C$  interface leaves state C8H, enters the not addressed slave receiver mode, and the SDA line remains at a high level. In state C8H, the AA flag can be set again for future address recognition.

When the  $\rm I^2C$  interface is in the not addressed slave mode, its own slave address and the general call address are ignored. Consequently, no acknowledge is returned, and a serial interrupt is not requested. Thus, the hardware can be temporarily released from the  $\rm I^2C$  bus while the bus status is monitored. While the hardware is released from the bus, START and STOP conditions are detected, and serial data is shifted in. Address recognition can be resumed at any time by setting the AA flag. If the AA flag is set when the part's own slave address or the general call address has been partly received, the address will be recognized at the end of the byte transmission.

XA 16-bit microcontroller 32 K/1 K OTP/ROM/ROMless, 8-channel 8-bit A/D, low voltage (2.7 V–5.5 V), I<sup>2</sup>C, 2 UARTs, 16 MB address range

XA-S3

#### CR0, CR1, and CR2, the Clock Rate Bits

These three bits determine the serial clock frequency when the  $I^2C$  interface is in a master mode. An  $I^2C$  rate of 100kHz or lower is typical and can be derived from many oscillator frequencies. The various serial rates are shown in Table 4. A variable bit rate may also be used if Timer 1 is not required for any other purpose while the  $I^2C$  hardware is in a master mode. The frequencies shown in Table 4 are unimportant when the  $I^2C$  hardware is in a slave mode. In the slave modes, the hardware will automatically synchronize with the incoming clock frequency.

## The I<sup>2</sup>C Status Register, I2STA

I2STA is an 8-bit read-only special function register. The three least significant bits are always zero. The five most significant bits contain the status code. There are 26 possible status codes. When I2STA contains F8H, no relevant state information is available and no serial interrupt is requested. All other I2STA values correspond to defined hardware interface states. When each of these states is entered, a serial interrupt is requested (SI = "1").

NOTE: A detailed I<sup>2</sup>C interface description and usage information, including example driver code, will be provided in a separate document.

Table 4. I<sup>2</sup>C Rate Control

Frequency Select	Clock Divisor		Example l <sup>2</sup>	C Rates at Spec	ific Oscillator Fr	equencies	
(CR2, CR1, CR0)	Clock Divisor	8 MHz	12 MHz	16 MHz	20 MHz	24 MHz	30 MHz
0h (0000)	20	(400) <sup>1</sup>	-	-	-	-	-
1h (0001)	40	(200) <sup>1</sup>	(300) <sup>1</sup>	(400) <sup>1</sup>	-	-	-
2h (0010)	68	(116.65) <sup>1</sup>	(176.46) <sup>1</sup>	(235.29) <sup>1</sup>	(294.12) <sup>1</sup>	(352.94) <sup>1</sup>	-
3h (0011)	88	90.91	(136.36) <sup>1</sup>	(181.82) <sup>1</sup>	(227.27)1	(272.73)1	(340.91) <sup>1</sup>
4h (0100)	160	50	75	100	(125) <sup>1</sup>	(150) <sup>1</sup>	(187.5) <sup>1</sup>
5h (0101)	272	29.41	44.12	58.82	73.53	88.24	(110.29) <sup>1</sup>
6h (0110)	352	22.73	34.09	45.45	56.82	68.18	85.23
7h (0111)	(Timer 1) <sup>2</sup>						

#### NOTES:

<sup>1.</sup> The XA-S3 I<sup>2</sup>C interface does not conform to the 400kHz I<sup>2</sup>C specification (which applies to rates greater than 100kHz) in all details, but may be used with care where higher rates are required by the application.

<sup>2.</sup> The timer 1 overflow is used to clock the I<sup>2</sup>C interface. The resulting bit rate is 1/2 of the timer overflow rate.

XA-S3

#### XA-S3 Timer/Counters

The XA-S3 has three general purpose counter/timers, two of which may also be used as baud rate generators for either or both of the UARTs.

#### Timer 0 and 1

These are identical to the standard XA-G3 timer 0 and 1.

#### Timer 2

This is identical to the standard XA-G3 timer 2.

## **Programmable Counter Array (PCA)**

The Programmable Counter Array available on the XA-S3 is a special 16-bit Timer that has five 16-bit capture/compare modules associated with it. Each of the modules can be programmed to operate in one of four modes: rising and/or falling edge capture, software timer, high-speed output, or pulse width modulator. Each module has a pin associated with it in port 1. Module 0 is connected to P4.1(CEX0), module 1 to P4.2(CEX1), etc. The basic PCA configuration is shown in Figure 7.

The PCA timer is a common time base for all five modules and can be programmed to run at: the TCLK rate (Osc/4, Osc/16, or Osc/64), the Timer 0 overflow, or the input on the ECI pin (P4.0). When the ECI input is used, the falling edge clocks the PCA counter. The timer count source is determined from the CPS1 and CPS0 bits in the CMOD SFR as follows (see Figure 10):

#### CPS1 CPS0 PCA Timer Count Source

- 0 X TCLK (Osc/4, Osc/16, or Osc/64)
- 1 0 Timer 0 overflow
- 1 1 ECI (PCA External Clock Input (max rate = Osc/4)

In the CMOD SFR are three additional bits associated with the PCA. They are CIDL which allows the PCA to stop during idle mode, WDTE which enables or disables the watchdog function on module 4, and ECF which when set causes an interrupt and the PCA overflow flag CF (in the CCON SFR) to be set when the PCA timer overflows. These functions are shown in Figure 8. In addition, each PCA module may generate a separate interrupt.

The watchdog timer function is implemented in module 4 (see Figure 17).

The CCON SFR contains the run control bit for the PCA and the flags for the PCA timer (CF) and each module (refer to Figure 11). To run the PCA the CR bit (CCON.6) must be set by software. The PCA is shut off by clearing this bit. The CF bit (CCON.7) is set when the PCA counter overflows and an interrupt will be generated if the ECF bit in the CMOD register is set, The CF bit can only be cleared by software. Bits 0 through 4 of the CCON register are the flags for the modules (bit 0 for module 0, bit 1 for module 1, etc.) and are set by hardware when either a match or a capture occurs. These flags also can only be cleared by software. The PCA interrupt system shown in Figure 9.

Each module in the PCA has a special function register associated with it. These registers are: CCAPM0 for module 0, CCAPM1 for module 1, etc. (see Figure 12). The registers contain the bits that control the mode that each module will operate in. The ECCF bit (CCAPMn.0 where n=0, 1, 2, 3, or 4 depending on the module) enables the CCF flag in the CCON SFR to generate an interrupt when a match or compare occurs in the associated module. PWM (CCAPMn.1) enables the pulse width modulation mode. The TOG bit (CCAPMn.2) when set causes the CEX output associated with the module to toggle when there is a match between the PCA counter and the module's capture/compare register. The match bit MAT (CCAPMn.3) when set will cause the CCFn bit in the CCON register to be set when there is a match between the PCA counter and the module's capture/compare register.

The next two bits CAPN (CCAPMn.4) and CAPP (CCAPMn.5) determine the edge that a capture input will be active on. The CAPN bit enables the negative edge, and the CAPP bit enables the positive edge. If both bits are set both edges will be enabled and a capture will occur for either transition. The last bit in the register ECOM (CCAPMn.6) when set enables the comparator function. Figure 13 shows the CCAPMn settings for the various PCA functions.

There are two additional registers associated with each of the PCA modules. They are CCAPnH and CCAPnL and these are the registers that store the 16-bit count when a capture occurs or a compare should occur. When a module is used in the PWM mode these registers are used to control the duty cycle of the output.




Figure 7. Programmable Counter Array (PCA)




Figure 8. PCA Timer/Counter




Figure 9. PCA Interrupt System

XA-S3




Figure 10. CMOD: PCA Counter Mode Register




Figure 11. CCON: PCA Counter Control Register

2000 Dec 01 22

 $Downloaded \ from \ \underline{Elcodis.com} \ \ electronic \ components \ distributor$ 

XA-S3




Figure 12. CCAPMn: PCA Modules Compare/Capture Registers

_	ECOMn	CAPPn	CAPNn	MATn	TOGn	PWMn	ECCFn	MODULE FUNCTION
Х	0	0	0	0	0	0	0	No operation
Х	Х	1	0	0	0	0	Х	16-bit capture by a positive-edge trigger on CEXn
Х	Х	0	1	0	0	0	Х	16-bit capture by a negative trigger on CEXn
Х	Х	1	1	0	0	0	Х	16-bit capture by a transition on CEXn
Х	1	0	0	1	0	0	Х	16-bit Software Timer
Х	1	0	0	1	1	0	Х	16-bit High Speed Output
Х	1	0	0	0	0	1	0	8-bit PWM
Х	1	0	0	1	Х	0	Х	Watchdog Timer

Figure 13. PCA Module Modes (CCAPMn Register)

#### **PCA Capture Mode**

To use one of the PCA modules in the capture mode either one or both of the CCAPM bits CAPN and CAPP for that module must be set. The external CEX input for the module (on port 1) is sampled for a transition. When a valid transition occurs the PCA hardware loads the value of the PCA counter registers (CH and CL) into the module's capture registers (CCAPnL and CCAPnH). If the CCFn bit for the module in the CCON SFR and the ECCFn bit in the CCAPMn SFR are set then an interrupt will be generated. Refer to Figure 14.

#### 16-bit Software Timer Mode

The PCA modules can be used as software timers by setting both the ECOM and MAT bits in the modules CCAPMn register. The PCA timer will be compared to the module's capture registers and when a match occurs an interrupt will occur if the CCFn (CCON SFR) and the ECCFn (CCAPMn SFR) bits for the module are both set (see Figure 15).

#### **High Speed Output Mode**

In this mode the CEX output (on port 4) associated with the PCA module will toggle each time a match occurs between the PCA

counter and the module's capture registers. To activate this mode the TOG, MAT, and ECOM bits in the module's CCAPMn SFR must be set (see Figure 16).

#### **Pulse Width Modulator Mode**

All of the PCA modules can be used as PWM outputs. Figure 17 shows the PWM function. The frequency of the output depends on the source for the PCA timer. All of the modules will have the same frequency of output because they all share the PCA timer. The duty cycle of each module is independently variable using the module's capture register CCAPLn. When the value of the PCA CL SFR is less than the value in the module's CCAPLn SFR the output will be low, when it is equal to or greater than the output will be high. When CL overflows from FF to 00, CCAPLn is reloaded with the value in CCAPHn. the allows updating the PWM without glitches. The PWM and ECOM bits in the module's CCAPMn register must be set to enable the PWM mode.




Figure 14. PCA Capture Mode




Figure 15. PCA Compare Mode




Figure 16. PCA High Speed Output Mode




Figure 17. PCA PWM Mode

XA 16-bit microcontroller 32 K/1 K OTP/ROM/ROMless, 8-channel 8-bit A/D, low voltage (2.7 V–5.5 V), I<sup>2</sup>C, 2 UARTs, 16 MB address range

XA-S3




Figure 18. PCA Watchdog Timer m(Module 4 only)

#### **PCA Watchdog Timer**

An on-board watchdog timer is available with the PCA to improve the reliability of the system without increasing chip count. Watchdog timers are useful for systems that are susceptible to noise, power glitches, or electrostatic discharge. Module 4 is the only PCA module that can be programmed as a watchdog. However, this module can still be used for other modes if the watchdog is not needed.

Figure 18 shows a diagram of how the watchdog works. The user pre-loads a 16-bit value in the compare registers. Just like the other compare modes, this 16-bit value is compared to the PCA timer value. If a match is allowed to occur, an internal reset will be generated. This will not cause the RST pin to be driven low.

In order to hold off the reset, the user has three options:

- periodically change the compare value so it will never match the PCA timer,
- 2. periodically change the PCA timer value so it will never match the compare values, or
- disable the watchdog by clearing the WDTE bit before a match occurs and then re-enable it.

The first two options are more reliable because the watchdog timer is never disabled as in option #3. If the program counter ever goes astray, a match will eventually occur and cause an internal reset. The second option is also not recommended if other PCA modules are being used. Remember, the PCA timer is the time base for **all** modules; changing the time base for other modules would not be a good idea. Thus, in most applications the first solution is the best option.

Figure 19 shows the code for initializing the watchdog timer. Module 4 can be configured in either compare mode, and the WDTE bit in CMOD must also be set. The user's software then must periodically change (CCAP4H,CCAP4L) to keep a match from occurring with the PCA timer (CH,CL). This code is given in the WATCHDOG routine in Figure 19.

This routine should not be part of an interrupt service routine, because if the program counter goes astray and gets stuck in an infinite loop, interrupts will still be serviced and the watchdog will keep getting reset. Thus, the purpose of the watchdog would be defeated. Instead, call this subroutine from the main program within  $2^{16}$  count of the PCA timer.

XA-S3

```
INIT_WATCHDOG:
  MOV CCAPM4, #4CH
                        ; Module 4 in compare mode
  MOV CCAP4L, #0FFH
                        ; Write to low byte first
  MOV CCAP4H, #0FFH
                        ; Before PCA timer counts up to
                         ; FFFF Hex, these compare values
                         ; must be changed
  OR CMOD, #40H
                         ; Set the WDTE bit to enable the
                         ; watchdog timer without changing
                         ; the other bits in CMOD
; Main program goes here, but CALL WATCHDOG periodically.
WATCHDOG:
                        ; Hold off interrupts
  CLR EA
  MOV CCAP4L, #00
                        ; Next compare value is within
                         ; 255 counts of the current PCA
  MOV CCAP4H, CH
  SETB EA
                         ; timer value
  RET
```

Figure 19. PCA Watchdog Timer Initialization Code

## Watchdog Timer

This is a standard XA-G3 watchdog timer. This watchdog timer always comes up running at reset. The watchdog acts the same on EPROM, ROM, and ROMless parts, as in the XA-G3.

#### **UARTS**

Standard XA-S3 UART0 and UART1 with double buffered transmit register. A flag has been added to SnSTAT that is set if any of the status flags (BRn, FEn, or OEn) is set for the corresponding UART channel. This allows polling for UART errors quickly at the interrupt service routine. Baud rate sources may be timer 1 or timer 2.

The XA-S3 includes 2 UART ports that are compatible with the enhanced UART used on the XA-G3.

The UART has separate interrupt vectors for each UART's transmit and receive functions. The UART transmitter has been double buffered, allowing packed transmission of data with no gaps between bytes and less critical interrupt service routine timing. A break detect function has been added to the UART. This operates independently of the UART itself and provides a start-of-break status bit that the program may test. An Overrun Error flag allows detection of missed characters in the received data stream. The double buffered UART transmitter may require some software changes if code is used that was written for the original XA-G3 single buffered UART.

Each UART baud rate is determined by either a fixed division of the oscillator (in UART modes 0 and 2) or by the timer 1 or timer 2 overflow rate (in UART modes 1 and 3).

Timer 1 defaults to clock both UART0 and UART1. Timer 2 can be programmed to clock either UART0 through T2CON (via bits R0CLK and T0CLK) or UART1 through T2MOD (via bits R1CLK and T1CLK). In this case, the UART not clocked by T2 could use T1 as the clock source.

The serial port receive and transmit registers are both accessed at Special Function Register SnBUF. Writing to SnBUF loads the

transmit register, and reading SnBUF accesses a physically separate receive register.

The serial port can operate in 4 modes:

**Mode 0: Serial I/O expansion mode.** Serial data enters and exits through RxDn. TxDn outputs the shift clock. 8 bits are transmitted/received (LSB first). (The baud rate is fixed at 1/16 the oscillator frequency.)

**Mode 1: Standard 8-bit UART mode.** 10 bits are transmitted (through TxDn) or received (through RxDn): a start bit (0), 8 data bits (LSB first), and a stop bit (1). On receive, the stop bit goes into RB8 in Special Function Register SnCON. The baud rate is variable.

Mode 2: Fixed rate 9-bit UART mode. 11 bits are transmitted (through TxD) or received (through RxD): start bit (0), 8 data bits (LSB first), a programmable 9th data bit, and a stop bit (1). On Transmit, the 9th data bit (TB8\_n in SnCON) can be assigned the value of 0 or 1. Or, for example, the parity bit (P, in the PSW) could be moved into TB8\_n. On receive, the 9th data bit goes into RB8\_n in Special Function Register SnCON, while the stop bit is ignored. The baud rate is programmable to 1/32 of the oscillator frequency.

**Mode 3: Standard 9-bit UART mode.** 11 bits are transmitted (through TxDn) or received (through RxDn): a start bit (0), 8 data bits (LSB first), a programmable 9th data bit, and a stop bit (1). In fact, Mode 3 is the same as Mode 2 in all respects except baud rate. The baud rate in Mode 3 is variable.

In all four modes, transmission is initiated by any instruction that uses SnBUF as a destination register. Reception is initiated in Mode 0 by the condition  $RI_n = 0$  and  $REN_n = 1$ . Reception is initiated in the other modes by the incoming start bit if  $REN_n = 1$ .

XA 16-bit microcontroller 32 K/1 K OTP/ROM/ROMless, 8-channel 8-bit A/D, low voltage (2.7 V-5.5 V), I<sup>2</sup>C, 2 UARTs, 16 MB address range

XA-S3

#### Serial Port Control Register

The serial port control and status register is the Special Function Register SnCON, shown in Figure 21. This register contains not only the mode selection bits, but also the 9th data bit for transmit and receive (TB8\_n and RB8\_n), and the serial port interrupt bits (TI\_n and RI\_n).

#### TI Flag

In order to allow easy use of the double buffered UART transmitter feature, the TI\_n flag is set by the UART hardware under two conditions. The first condition is the completion of any byte transmission. This occurs at the end of the stop bit in modes 1, 2, or 3, or at the end of the eighth data bit in mode 0. The second condition is when SnBUF is written while the UART transmitter is idle. In this case, the TI\_n flag is set in order to indicate that the second UART transmitter buffer is still available.

Typically, UART transmitters generate one interrupt per byte transmitted. In the case of the XA UART, one additional interrupt is generated as defined by the stated conditions for setting the TI\_n flag. This additional interrupt does not occur if double buffering is bypassed as explained below. Note that if a character oriented approach is used to transmit data through the UART, there could be a second interrupt for each character transmitted, depending on the timing of the writes to SBUF. For this reason, it is generally better to bypass double buffering when the UART transmitter is used in character oriented mode. This is also true if the UART is polled rather than interrupt driven, and when transmission is character oriented rather than message or string oriented. The interrupt occurs at the end of the last byte transmitted when the UART becomes idle. Among other things, this allows a program to determine when a message has been transmitted completely. The interrupt service routine should handle this additional interrupt.

The recommended method of using the double buffering in the application program is to have the interrupt service routine handle a single byte for each interrupt occurrence. In this manner the program essentially does not require any special considerations for double buffering. Unless higher priority interrupts cause delays in the servicing of the UART transmitter interrupt, the double buffering will result in transmitted bytes being tightly packed with no intervening gaps.

#### 9-bit Mode

Please note that the ninth data bit (TB8) is not double buffered. Care must be taken to insure that the TB8 bit contains the intended data at the point where it is transmitted. Double buffering of the UART transmitter may be bypassed as a simple means of synchronizing TB8 to the rest of the data stream.

## **Bypassing Double Buffering**

The UART transmitter may be used as if it is single buffered. The recommended UART transmitter interrupt service routine (ISR) technique to bypass double buffering first clears the TI\_n flag upon entry into the ISR, as in standard practice. This clears the interrupt that activated the ISR. Secondly, the TI\_n flag is cleared immediately following each write to SnBUF. This clears the interrupt flag that would otherwise direct the program to write to the second transmitter buffer. If there is any possibility that a higher priority interrupt might become active between the write to SnBUF and the clearing of the TI\_n flag, the interrupt system may have to be temporarily disabled during that sequence by clearing, then setting the EA bit in the IEL register.

#### **CLOCKING SCHEME/BAUD RATE GENERATION**

The XA UARTS clock rates are determined by either a fixed division (modes 0 and 2) of the oscillator clock or by the Timer 1 or Timer 2 overflow rate (modes 1 and 3).

The clock for the UARTs in XA runs at 16x the Baud rate. If the timers are used as the source for Baud Clock, since maximum speed of timers/Baud Clock is Osc/4, the maximum baud rate is timer overflow divided by 16 i.e. Osc/64.

In Mode 0, it is fixed at Osc/16. In Mode 2, however, the fixed rate is Osc/32.

	00	Osc/4
Pre-scaler	01	Osc/16
for all Timers T0,1,2 controlled by PT1, PT0	10	Osc/64
bits in SCR	11	reserved

#### Baud Rate for UART Mode 0:

Baud Rate = Osc/16

#### Baud Rate calculation for UART Mode 1 and 3:

Baud\_Rate = Timer\_Rate/16

Timer\_Rate = Osc/(N\*(Timer\_Range-Timer\_Reload\_Value))

where N = the TCLK prescaler value: 4, 16, or 64. and Timer\_Range = 256 for timer 1 in mode 2.

65536 for timer 1 in mode 0 and timer 2 in count up mode.

The timer reload value may be calculated as follows: Timer\_Reload\_Value = Timer\_Range-(Osc/(Baud\_Rate\*N\*16))

#### **NOTES**

- 1.. The maximum baud rate for a UART in mode 1 or 3 is Osc/64.
- The lowest possible baud rate (for a given oscillator frequency and N value) may be found by using a timer reload value of 0.
- 3.. The timer reload value may never be larger than the timer range.
- 4.. If a timer reload value calculation gives a negative or fractional result, the baud rate requested is not possible at the given oscillator frequency and N value.

#### Baud Rate for UART Mode 2:

Baud\_Rate = Osc/32

#### **Using Timer 2 to Generate Baud Rates**

Timer T2 is a 16-bit up/down counter in XA. As a baud rate generator, timer 2 is selected as a clock source for either/both UART0 and UART1 transmitters and/or receivers by setting TCLKn and/or RCLKn in T2CON and T2MOD. As the baud rate generator, T2 is incremented as Osc/N where N = 4, 16 or 64 depending on TCLK as programmed in the SCR bits PT1, and PTO. So, if T2 is the source of one UART, the other UART could be clocked by either T1 overflow or fixed clock, and the UARTs could run independently with different baud rates.

T2CON	bit5	bit4	
0x418	RCLK0	TCLK0	
T2MOD	bit5	bit4	
0x419	RCLK1	TCLK1	

#### Prescaler Select for Timer Clock (TCLK)

	 `	,	
SCR	bit3	bit2	
0x440	PT1	PT0	

XA-S3

SnSTAT Address	: S0STAT 4 S1STAT 4	0.5	MSB							LSB	
Bit Addressable Reset Value: 00H			_	_	_	_	FEn	BRn	OEn	STINTn	
ВІТ	SYMBOL	FUNCTI	ION								
SnSTAT.3	FEn		Error fla by softw		nen the re	ceiver fail	s to see a	valid STC	OP bit at tl	he end of t	he frame.
SnSTAT.2	BRn	it gives a feature o	a "Start o operates	f Break Doi	etect" on be ently of the	oit 8 for Mo	ode 1 and and provid	bit 9 for N	∕lodes 2 a	nd 3. The	ng logic '0'. Thus break detect ct status bit that
SnSTAT.1	OEn	the softv	ware has	read the p	revious c		rom the bi	uffer), i.e.,		while it is 8 of a new	still full (before byte is
SnSTAT.0	STINTn					of the above ftware writ			nerate a ı	receive int	errupt (RIn). The SU00607B

Figure 20. Serial Port Extended Status (SnSTAT) Register (See also Figure 22 regarding Framing Error flag)

#### **UART INTERRUPT SCHEME**

There are separate interrupt vectors for each UART's transmit and receive functions.

Table 5. Interrupt Vector Locations for UARTs

Vector Address	Interrupt Source	Arbitration
A0H – A3H	UART 0 Receiver	9
A4H – A7H	UART 0 Transmitter	10
A8H – ABH	UART 1 Receiver	11
ACH – AFH	UART 1 Transmitter	12

#### NOTE:

The transmit and receive vectors could contain the same ISR address to work like a 8051 interrupt scheme

#### **Error Handling, Status Flags and Break Detect**

XA UARTs have several error flags as described in Figures 20 and 22.

#### **Multiprocessor Communications**

Modes 2 and 3 have a special provision for multiprocessor communications. In these modes, 9 data bits are received. The 9th one goes into RB8. Then comes a stop bit. The port can be programmed such that when the stop bit is received, the serial port interrupt will be activated only if RB8 = 1. This feature is enabled by setting bit SM2 in SCON. A way to use this feature in multiprocessor systems is as follows:

When the master processor wants to transmit a block of data to one of several slaves, it first sends out an address byte which identifies the target slave. An address byte differs from a data byte in that the 9th bit is 1 in an address byte and 0 in a data byte. With SM2 = 1, no slave will be interrupted by a data byte. An address byte, however, will interrupt all slaves, so that each slave can examine the received byte and see if it is being addressed. The addressed slave will clear its SM2 bit and prepare to receive the data bytes that will be coming. The slaves that weren't being addressed leave their SM2s set and go on about their business, ignoring the coming data bytes.

SM2 has no effect in Mode 0, and in Mode 1 can be used to check the validity of the stop bit although this is better done with the Framing Error (FE) flag. In a Mode 1 reception, if SM2 = 1, the receive interrupt will not be activated unless a valid stop bit is received.

#### **Automatic Address Recognition**

Automatic Address Recognition is a feature which allows the UART to recognize certain addresses in the serial bit stream by using hardware to make the comparisons. This feature saves a great deal of software overhead by eliminating the need for the software to examine every serial address which passes by the serial port. This feature is enabled by setting the SM2 bit in SCON. In the 9 bit UART modes, mode 2 and mode 3, the Receive Interrupt flag (RI) will be automatically set when the received byte contains either the "Given" address or the "Broadcast" address. The 9 bit mode requires that the 9th information bit is a 1 to indicate that the received information is an address and not data. Automatic address recognition is shown in Figure 23.

Using the Automatic Address Recognition feature allows a master to selectively communicate with one or more slaves by invoking the Given slave address or addresses. All of the slaves may be contacted by using the Broadcast address. Two special Function Registers are used to define the slave's address, SADDR, and the address mask, SADEN. SADEN is used to define which bits in the SADDR are to be used and which bits are "don't care". The SADEN mask can be logically ANDed with the SADDR to create the "Given" address which the master will use for addressing each of the slaves. Use of the Given address allows multiple slaves to be recognized while excluding others. The following examples will help to show the versatility of this scheme:

Slave 0	SADDR	=	1100 0000
	SADEN	=	<u>1111 1101</u>
	Given	=	1100 00X0
Slave 1	SADDR	=	1100 0000
	SADEN	=	<u>1111 1110</u>
	Given	=	1100 000X

In the above example SADDR is the same and the SADEN data is used to differentiate between the two slaves. Slave 0 requires a 0 in bit 0 and it ignores bit 1. Slave 1 requires a 0 in bit 1 and bit 0 is ignored. A unique address for Slave 0 would be 1100 0010 since slave 1 requires a 0 in bit 1. A unique address for slave 1 would be

XA-S3

1100 0001 since a 1 in bit 0 will exclude slave 0. Both slaves can be selected at the same time by an address which has bit 0=0 (for slave 0) and bit 1=0 (for slave 1). Thus, both could be addressed with 1100 0000.

In a more complex system the following could be used to select slaves 1 and 2 while excluding slave 0:

Slave 0	SADDR	=	1100 0000
	SADEN	=	1111 1001
	Given	=	1100 0XX0
Slave 1	SADDR	=	1110 0000
	SADEN	=	1111 1010
	Given	=	1110 0X0X
Slave 2	SADDR	=	1110 0000
	SADEN	=	1111 1100
	Given	=	1110 00XX

In the above example the differentiation among the 3 slaves is in the lower 3 address bits. Slave 0 requires that bit 0=0 and it can be uniquely addressed by 1110 0110. Slave 1 requires that bit 1=0 and it can be uniquely addressed by 1110 and 0101. Slave 2 requires that bit 2=0 and its unique address is 1110 0011. To select Slaves 0 and 1 and exclude Slave 2 use address 1110 0100, since it is necessary to make bit 2=1 to exclude slave 2.

The Broadcast Address for each slave is created by taking the logical OR of SADDR and SADEN. Zeros in this result are teated as don't-cares. In most cases, interpreting the don't-cares as ones, the broadcast address will be FF hexadecimal.

Upon reset SADDR and SADEN are loaded with 0s. This produces a given address of all "don't cares" as well as a Broadcast address of all "don't cares". This effectively disables the Automatic Addressing mode and allows the microcontroller to use standard UART drivers which do not make use of this feature.

SnCON	Address:	S0CON 420									
		S1CON 424	MS	В						LSB	
Bit Address	sable		SM	0 SN	11 SM2	REN	TB8	RB8	TI	RI	
Reset Valu	e: 00H										
		Where S	M0, SM1	specify th	ne serial port m	ode, as fo	ollows:				
		SM0	SM1	Mode	Description	Bau	d Rate				
		0	0	0	shift register	fos	<sub>C</sub> /16				
		0	1	1	8-bit UART	var	iable				
		1	0	2	9-bit UART	fos	<sub>C</sub> /32				
		1	1	3	9-bit UART	var	iable				
BIT	SYMBOL	FUNCTION									
SnCON.5	SM2	Enables the multiprical will not be activated walld stop bit was n	I if the rec	eived 9th		is 0. In N					
		valid Stop bit was it									
SnCON.4	REN	Enables serial rece	ption. Set	by softwa	are to enable re	eception.	Clear by	software to	o disable r	eception.	
SnCON.4 SnCON.3	REN TB8	'	t will be tr	ansmitte			•				88 bit is not
	TB8	Enables serial rece The 9th data bit tha	t will be tree text for sthe 9th (	ansmitted details. data bit th	d in Modes 2 a	nd 3. Set	or clear b	y software	as desire	ed. The TE	
SnCON.3	TB8	Enables serial rece The 9th data bit tha double buffered. Se In Modes 2 and 3, i	t will be tree text for s the 9th or RB8 is rag. Set w	ransmitted details. data bit th not used. hen anotl	d in Modes 2 an	nd 3. Set	or clear b	y software	as desire	ed. The TE	vas
SnCON.3 SnCON.2	TB8 RB8 TI	Enables serial rece The 9th data bit tha double buffered. Se In Modes 2 and 3, received. In Mode ( Transmit interrupt f	t will be tree text for s the 9th of the 9th of the grant ag. Set we software.	ansmitted details. data bit th not used. hen anoth	d in Modes 2 and the mat was received the her byte may be at the end of	nd 3. Set  d. In Mod  written  the 8th b	or clear be the second or clear be	y software I2=0, RB8 RT transm	e as desire is the sto itter. See	ed. The TE p bit that v	vas tails.

Figure 21. Serial Port Control (SnCON) Register

XA-S3




Figure 22. UART Framing Error Detection




Figure 23. UART Multiprocessor Communication, Automatic Address Recognition

## Clocking / Baud Rate Generation

Same as for the XA-G3.

#### I/O Port Output Configuration

Port output configurations are the same as for the XA-G3: open drain, quasi-bidirectional, push-pull, and off.

#### **External Bus**

The external bus operates in the same manner as the XA-G3, but all 24 address lines are brought out to the outside world. This allows for a maximum of 16 Mbytes of code memory and 16 Mbytes of data memory.

#### **Clock Output**

The CLKOUT pin allows easier external bus interfacing in some situations. This output reflects the X1 clock input to the XA, but is delayed to match the external bus outputs and strobes. The default is for CLKOUT to be on at reset, but it may be turned off via the CLKD bit that has been added to the BCR register.

#### Reset

Active low reset input, the same as the XA-G3.

Downloaded from Elcodis.com electronic components distributor

The associated RSTOUT pin provides an external indication via an active low open drain output when an internal reset occurs. The RSTOUT pin will be driven low when the RST pin is driven low, when a Watchdog reset occurs or the RESET instruction is executed. This signal may be used to inform other devices in a system that the XA-S3 has been reset.

The latched values of  $\overline{EA}$  and BUSW are NOT automatically updated when an internal reset occurs.  $\overline{RSTOUT}$  may be used to apply an external reset to the XA-S3 in order to update the previously latched  $\overline{EA}$  and BUSW values. However, since  $\overline{RSTOUT}$  reflects ALL reset sources, it cannot simply be fed back into the  $\overline{RSTOUT}$  pin without other logic.

The reset source identification register (RSTSRC) indicates the cause of the most recent XA reset. The cause may have been an externally applied reset signal, execution of the RESET instruction, or a Watchdog reset. Figure 24 shows the fields in the RSTSRC register.

#### **Power Reduction Modes**

The XA-S3 supports Idle and Power Down modes of power reduction. The idle mode leaves some peripherals running in order to allow them to activate the processor when an interrupt is generated. The power down mode stops the oscillator in order to absolutely minimize power. The processor can be made to exit power down mode via a reset or one of the external interrupt inputs (INT0 or INT1). This will occur if the interrupt is enabled and its priority is higher than that defined by IM3 through IM0. In power down mode, the power supply voltage may be reduced to the RAM keep-alive voltage  $V_{RAM}.$  This retains the RAM, register, and SFR contents at the point where power down mode was entered.  $V_{DD}$  must be raised to within the operating range before power down mode is exited.

XA 16-bit microcontroller 32 K/1 K OTP/ROM/ROMless, 8-channel 8-bit A/D, low voltage (2.7 V–5.5 V), I<sup>2</sup>C, 2 UARTs, 16 MB address range

XA-S3

RSTSRC Addres	s:463h	MSB LSB								
Not bit Addressable Reset Value: see bel	ow		_	_	_	_	R_WD	R_CMD	R_EXT	
BIT	SYMBOL	FUNCTIO	N							
RSTSRC.7	_	Reserved	Reserved for future use. Should not be set to 1 by user programs.							
RSTSRC.6	_	Reserved for future use. Should not be set to 1 by user programs.								
RSTSRC.5	_	Reserved	for future	use. Shou	uld not be	set to 1 b	y user pro	grams.		
RSTSRC.4	_	Reserved	for future	use. Shou	uld not be	set to 1 b	y user pro	grams.		
RSTSRC.3	_	Reserved	for future	use. Shou	uld not be	set to 1 b	y user pro	grams.		
RSTSRC.2	R_WD	Indicates	that the la	st reset w	as caused	by a wat	chdog tim	er overflov	N.	
RSTSRC.1	R_CMD	Indicates	that the la	st reset w	as caused	by execu	ution of the	RESET i	instruction	
RSTSRC.0	R_EXT	Indicates	that the la	st reset w	as caused	by the ex	xternal RS	T input.		
									SU00:	

Figure 24. Reset source register (RSTSRC)

#### **INTERRUPTS**

XA-S3 interrupt sources include the following:

- External interrupts 0 and 1 (2)
- Timer 0, 1, and 2 interrupts (3)
- PCA: 1 global and 5 channel interrupts (6)
- A/D interrupt (1)
- UART 0 transmitter and receiver interrupts (2)
- UART 1 transmitter and receiver interrupts (2)
- I<sup>2</sup>C interrupt (1)
- Software interrupts (7)

There are a total of 17 **hardware** interrupt sources, enable bits, priority bit sets, etc.

The XA-S3 supports a total of 17 maskable event interrupt sources (for the various XA peripherals), seven software interrupts, 5

exception interrupts (plus reset), and 16 traps. The maskable event interrupts share a global interrupt disable bit (the EA bit in the IEL register) and each also has a separate individual interrupt enable bit (in the IEL or IEH registers). Only three bits of the IPA register values are used on the XA-S3. Each event interrupt can be set to occur at one of 8 priority levels via bits in the Interrupt Priority (IP) registers, IPA0 through IPA5. The value 0 in the IPA field gives the interrupt priority 0, in effect disabling the interrupt. A value of 1 gives the interrupt a priority of 9, the value 2 gives priority 10, etc. The result is the same as if all four bits were used and the top bit set for all values except 0. Details of the priority scheme may be found in the XA User Guide.

The complete interrupt vector list for the XA-S3, including all 4 interrupt types, is shown in the following tables. The tables include the address of the vector for each interrupt, the related priority register bits (if any), and the arbitration ranking for that interrupt source. The arbitration ranking determines the order in which interrupts are processed if more than one interrupt of the same priority occurs simultaneously.

#### **EXCEPTION/TRAPS PRECEDENCE**

DESCRIPTION	VECTOR ADDRESS	ARBITRATION RANKING
Reset (h/w, watchdog, s/w)	0000-0003	0 (High)
Breakpoint	0004–0007	1
Trace	0008-000B	1
Stack Overflow	000C-000F	1
Divide by 0	0010–0013	1
User RETI	0014–0017	1
TRAP 0-15 (software)	0040-007F	1

XA 16-bit microcontroller 32 K/1 K OTP/ROM/ROMless, 8-channel 8-bit A/D, low voltage (2.7 V–5.5 V),  $I^2C$ , 2 UARTs, 16 MB address range

XA-S3

## **EVENT INTERRUPTS**

DESCRIPTION	FLAG BIT	VECTOR ADDRESS	ENABLE BIT	INTERRUPT PRIORITY	ARBITRATION RANKING
External Interrupt 0	IE0	0080-0083	EX0	IPA0.2-0 (PX0)	2
Timer 0 Interrupt	TF0	0084–0087	ET0	IPA0.6-4 (PT0)	3
External Interrupt 1	IE1	0088-008B	EX1	IPA1.2-0 (PX1)	4
Timer 1 Interrupt	TF1	008C-008F	ET1	IPA1.6-4 (PT1)	5
Timer 2 Interrupt	TF2 (EXF2)	0090-0093	ET2	IPA2.2-0 (PT2)	6
PCA Interrupt	CCF0-CCF4, CF	0094–0097	EPC	IPA2.6-4 (PPC)	7
A/D Interrupt	ADINT	0098-009B	EAD	IPA3.2-0 (PAD)	8
Serial Port 0 Rx	RI_0	00A0-00A3	ERI0	IPA4.2-0 (PRI0)	9
Serial Port 0 Tx	TI_0	00A4-00A7	ETI0	IPA4.6-4 (PTI0)	10
Serial Port 1 Rx	RI_1	00A8-00AB	ERI1	IPA5.2-0 (PRI1)	11
Serial Port 1 Tx	TI_1	00AC-00AF	ETI1	IPA5.6-4 (PTI1)	12
PCA channel 0	CCF0	00C0-00C3	EC0	IPB0.2-0 (PC0)	17
PCA channel 1	CCF1	00C4-00C7	EC1	IPB0.6-4 (PC1)	18
PCA channel 2	CCF2	00C8-00CB	EC2	IPB1.2-0 (PC2)	19
PCA channel 3	CCF3	00CC-00CF	EC3	IPB1.6-4 (PC3)	20
PCA channel 4	CCF4	00D0-00D3	EC4	IPB2.2-0 (PC4)	21
I <sup>2</sup> C Interrupt	SI	00D4-00D7	El2	IPB2.6-4 (PI2)	22

## **SOFTWARE INTERRUPTS**

DESCRIPTION	FLAG BIT	VECTOR ADDRESS	ENABLE BIT	INTERRUPT PRIORITY
Software Interrupt 1	SWR1	0100-0103	SWE1	(fixed at 1)
Software Interrupt 2	SWR2	0104–0107	SWE2	(fixed at 2)
Software Interrupt 3	SWR3	0108-010B	SWE3	(fixed at 3)
Software Interrupt 4	SWR4	010C-010F	SWE4	(fixed at 4)
Software Interrupt 5	SWR5	0110–0113	SWE5	(fixed at 5)
Software Interrupt 6	SWR6	0114–0117	SWE6	(fixed at 6)
Software Interrupt 7	SWR7	0118–011B	SWE7	(fixed at 7)

XA-S3

#### ABSOLUTE MAXIMUM RATINGS

PARAMETER	RATING	UNIT
Operating temperature under bias	-55 to +125	°C
Storage temperature range	-65 to +150	°C
Voltage on EA/V <sub>PP</sub> pin to V <sub>SS</sub>	0 to +13.0	V
Voltage on any other pin to V <sub>SS</sub>	–0.5 to V <sub>DD</sub> +0.5 V	V
Maximum I <sub>OL</sub> per I/O pin	15	mA
Power dissipation (based on package heat transfer, not device power consumption)	1.5	W

#### DC ELECTRICAL CHARACTERISTICS

V<sub>DD</sub> = 2.7 V to 5.5 V, unless otherwise specified.

 $T_{amb} = 0$  to +70°C for commercial,  $T_{amb} = -40$ °C to +85°C for industrial, unless otherwise specified.

SYMBOL	PARAMETER	TEGT COMPITIONS	LIMITS			
SYMBOL		TEST CONDITIONS	MIN	TYP	MAX	UNIT
I <sub>DD</sub>	Power supply current, operating	5.0 V, 30 MHz			80	mA
I <sub>ID</sub>	Power supply current, Idle mode	5.0 V, 30 MHz			35	mA
I <sub>PD</sub>	Power supply current, Power Down mode	5.0 V, 3.0 V		5	100	μΑ
		5.0 V, 3.0 V, -40 to +85°C			150	μΑ
V <sub>RAM</sub>	RAM keep-alive voltage		1.5			V
V <sub>IL</sub>	Input low voltage		-0.5		0.22 V <sub>DD</sub>	V
V <sub>IH</sub>	Input high voltage, except XTAL1, RST	V <sub>DD</sub> = 5.0 V	2.2			V
		V <sub>DD</sub> = 3.0 V	2.0			V
V <sub>IH1</sub>	Input high voltage to XTAL1, RST	For both 3.0 V and 5.0 V	0.7 V <sub>DD</sub>			V
V <sub>OL</sub>	Output low voltage, all ports, ALE, PSEN4, CLKOUT	$I_{OL} = 3.2 \text{ mA}, V_{DD} = 5.0 \text{ V}$			0.5	V
		$I_{OL} = 1.0 \text{ mA}, V_{DD} = 3.0 \text{ V}$			0.4	V
V <sub>OH1</sub>	Output high voltage, all ports, ALE, PSEN2, CLKOUT	$I_{OH} = -100 \mu\text{A},  V_{DD} = 4.5 \text{V}$	2.4			V
		$I_{OH} = -30 \mu A, V_{DD} = 2.7 V$	2.0			V
V <sub>OH2</sub>	Output high voltage, all ports ALE, PSEN <sup>3</sup> , CLKOUT	$I_{OH} = -3.2 \text{ mA}, V_{DD} = 4.5 \text{ V}$	2.4			V
		$I_{OH} = -1.0 \text{ mA}, V_{DD} = 2.7 \text{ V}$	2.2			V
C <sub>IO</sub>	Input/Output pin capacitance <sup>1</sup>				15	pF
I <sub>IL</sub>	Logical 0 input current, all ports <sup>7</sup>	V <sub>IN</sub> = 0.45 V			-50	μΑ
ILI	Input leakage current, all ports <sup>6</sup>	$V_{IN} = V_{IL} \text{ or } V_{IH}$			±10	μΑ
I <sub>TL</sub>	Logical 1 to 0 transition current, all ports <sup>5</sup>	At V <sub>DD</sub> = 5.5 V			-650	μΑ
		At V <sub>DD</sub> = 2.7 V			-250	μА

## NOTES:

- 1. Maximum 15pF for EA/V<sub>PP</sub>.
- 2. Ports in quasi-bidirectional mode with weak pullup (applies to ALE, PSEN only during RESET).
- 3. Ports in PUSH-PULL mode, both pullup and pulldown assumed to be the same strength.
- 4. In all output modes.
- Port pins source a transition current when used in quasi-bidirectional mode and externally driven from 1 to 0. This current is highest when V<sub>IN</sub> is approximately 2 V.
- 6. Measured with port in high impedance mode.
- 7. Measured with port in quasi-bidirectional mode.
- 8. Under steady state (non-transient) conditions,  $I_{\mbox{\scriptsize OL}}$  must be externally limited as follows:

If  $I_{OL}$  exceeds the test condition,  $V_{OL}$  may exceed the related specification. Pins are not guaranteed to sink current greater than the listed test conditions.

XA-S3

#### 8-BIT MODE A/D CONVERTER DC ELECTRICAL CHARACTERISTICS

 $T_{amb} = 0$  to +70°C for commercial,  $T_{amb} = -40$  to +85°C for industrial, unless otherwise specified.

SYMBOL	PARAMETER	TEST CONDITIONS	LI		
			MIN	MAX	UNIT
$AV_{DD}$	Analog supply voltage		2.7	3.3	V
Al <sub>DD</sub>	Analog supply current (operating)	Port 5 = 0 to AV <sub>DD</sub>		2.5	mA
Al <sub>ID</sub>	Analog supply current (Idle mode)			2.5	μΑ
Al <sub>PD</sub>	Analog supply current (Power-Down mode)	Commercial temperature range		100	μΑ
		Industrial temperature range		150	μΑ
AV <sub>IN</sub>	Analog input voltage		AV <sub>SS</sub> -0.2	AV <sub>DD</sub> +0.2	V
R <sub>REF</sub>	Resistance between V <sub>REF+</sub> and V <sub>REF-</sub>		125	225	kΩ
C <sub>IA</sub>	Analog input capacitance			15	pF
DL <sub>e</sub>	Differential non-linearity <sup>1, 2, 3</sup>			±1	LSB
IL <sub>e</sub>	Integral non-linearity <sup>1, 4</sup>			±1	LSB
OS <sub>e</sub>	Offset error <sup>1, 5</sup>			±2.5	LSB
G <sub>e</sub>	Gain error <sup>1, 6</sup>			±1	%
A <sub>e</sub>	Absolute voltage error <sup>1, 7</sup>			±3	LSB
M <sub>CTC</sub>	Channel-to-channel matching			±1	LSB
C <sub>t</sub>	Crosstalk between inputs of port8	0 – 100 kHz		-60	dB

- Conditions:  $AV_{REF-} = 0 \text{ V}$ ;  $AV_{REF+} = 3.07 \text{ V}$ . The differential non-linearity (DL<sub>e</sub>) is the difference between the actual step width and the ideal step width. See Figure 25.
- The ADC is monotonic, there are no missing codes.
- 4. The integral non-linearity (ILe) is the peak difference between the center of the steps of the actual and the ideal transfer curve after appropriate adjustment of gain and offset errors. See Figure 25.
- The offset error (OSe) is the absolute difference between the straight line which fits the actual transfer curve (after removing gain error), and the straight line which fits the ideal transfer curve. See Figure 25.
- 6. The gain error (Ge) is the relative difference in percent between the straight line fitting the actual transfer curve (after removing offset error), and the straight line which fits the ideal transfer curve. Gain error is constant at every point on the transfer curve. See Figure 25.
- 7. The absolute voltage error (Ae) is the maximum difference between the center of the steps of the actual transfer curve of the non-calibrated ADC and the ideal transfer curve.
- 8. This should be considered when both analog and digital signals are input simultaneously to Port 5. Parameter is guaranteed by design.

2000 Dec 01 35

XA-S3

## 10-BIT10 MODE A/D CONVERTER DC ELECTRICAL CHARACTERISTICS

 $T_{amb} = 0$  to +70°C for commercial,  $T_{amb} = -40$  to +85°C for industrial, unless otherwise specified.

SYMBOL	PARAMETER	TEST CONDITIONS	LI		
			MIN	MAX	UNIT
$AV_{DD}$	Analog supply voltage		2.7	3.3	V
Al <sub>DD</sub>	Analog supply current (operating)	Port 5 = 0 to AV <sub>DD</sub>		2.5	mA
Al <sub>ID</sub>	Analog supply current (Idle mode)			2.5	μΑ
Al <sub>PD</sub>	Analog supply current (Power-Down mode)	Commercial temperature range		100	μА
		Industrial temperature range		150	μΑ
AV <sub>IN</sub>	Analog input voltage		AV <sub>SS</sub> -0.2	AV <sub>DD</sub> +0.2	V
R <sub>REF</sub>	Resistance between V <sub>REF+</sub> and V <sub>REF-</sub>		125	225	kΩ
C <sub>IA</sub>	Analog input capacitance			15	pF
DL <sub>e</sub>	Differential non-linearity <sup>1, 2, 3</sup>			±1 <sup>9</sup>	LSB
IL <sub>e</sub>	Integral non-linearity <sup>1, 4</sup>			±2.5 <sup>9</sup>	LSB
OS <sub>e</sub>	Offset error <sup>1, 5</sup>			±6 <sup>9</sup>	LSB
G <sub>e</sub>	Gain error <sup>1, 6</sup>			±1 <sup>9</sup>	%
A <sub>e</sub>	Absolute voltage error (with averaging) <sup>1, 7</sup>			±8 <sup>9</sup>	LSB
M <sub>CTC</sub>	Channel-to-channel matching			±1	LSB
C <sub>t</sub>	Crosstalk between inputs of port <sup>8</sup>	0 – 100 kHz		-60	dB

- Conditions:  $AV_{REF-} = 0 \text{ V}$ ;  $AV_{REF+} = 3.07 \text{ V}$ . The differential non-linearity (DL<sub>e</sub>) is the difference between the actual step width and the ideal step width. See Figure 25.
- The ADC is monotonic, there are no missing codes.
- 4. The integral non-linearity (ILe) is the peak difference between the center of the steps of the actual and the ideal transfer curve after appropriate adjustment of gain and offset errors. See Figure 25.
- The offset error (OSe) is the absolute difference between the straight line which fits the actual transfer curve (after removing gain error), and the straight line which fits the ideal transfer curve. See Figure 25.
- 6. The gain error (Ge) is the relative difference in percent between the straight line fitting the actual transfer curve (after removing offset error), and the straight line which fits the ideal transfer curve. Gain error is constant at every point on the transfer curve. See Figure 25.
- 7. The absolute voltage error (A<sub>e</sub>) is the maximum difference between the center of the steps of the actual transfer curve of the non-calibrated ADC and the ideal transfer curve.
- This should be considered when both analog and digital signals are input simultaneously to Port 5. Parameter is guaranteed by design.
- 9. 10-bit mode only.
- 10.10-bit mode is only operational up to  $f_C = 20 \text{ MHz}$ .

2000 Dec 01 36




Figure 25. ADC Conversion Characteristic

XA-S3

AC ELECTRICAL CHARACTERISTICS (5 V)  $V_{DD} = 4.5 \text{ V to } 5.5 \text{ V; } T_{amb} = 0 \text{ to } +70 ^{\circ}\text{C for commercial, } T_{amb} = -40 ^{\circ}\text{C to } +85 ^{\circ}\text{C for industrial.}$ 

SYMBOL	FIGURE	PARAMETER	LIM	ITS	UNIT
STWIBUL	FIGURE	PARAMETER	MIN	MAX	UNIT
External C	lock				
$f_{\mathbb{C}}$	32	Oscillator frequency	0	30	MHz
$t_{C}$	32	Clock period and CPU timing cycle	1/f <sub>C</sub>		ns
t <sub>CHCX</sub>	32	Clock high-time (Note 7)	t <sub>C</sub> * 0.5		ns
t <sub>CLCX</sub>	32	Clock low time (Note 7)	t <sub>C</sub> * 0.4		ns
t <sub>CLCH</sub>	32	Clock rise time (Note 7)		5	ns
t <sub>CHCL</sub>	32	Clock fall time (Note 7)		5	ns
Address C	ycle	•			
t <sub>LHLL</sub>	26, 28, 30	ALE pulse width (programmable)	(V1 * t <sub>C</sub> ) - 6		ns
t <sub>AVLL</sub>	26, 28, 30	Address valid to ALE de-asserted (set-up)	(V1 * t <sub>C</sub> ) – 12		ns
t <sub>LLAX</sub>	26, 28, 30	Address hold after ALE de-asserted	$(t_{\rm C}/2) - 10$		ns
Code Read	l Cycle				
t <sub>PLPH</sub>	26	PSEN pulse width	(V2 * t <sub>C</sub> ) – 10		ns
t <sub>LLPL</sub>	26	ALE de-asserted to PSEN asserted	$(t_{\rm C}/2) - 7$		ns
t <sub>AVIVA</sub>	26	Address valid to instruction valid, ALE cycle (access time)		(V3 * t <sub>C</sub> ) – 36	ns
t <sub>AVIVB</sub>	27	Address valid to instruction valid, non-ALE cycle (access time)		(V4 * t <sub>C</sub> ) – 29	ns
t <sub>PLIV</sub>	26	PSEN asserted to instruction valid (enable time)		(V2 * t <sub>C</sub> ) – 29	ns
t <sub>PHIX</sub>	26	Instruction hold after PSEN de-asserted	0		ns
t <sub>PHIZ</sub>	26	Bus 3-State after PSEN de-asserted		t <sub>C</sub> – 8	ns
t <sub>IXUA</sub>	26	Hold time of unlatched part of address after instruction latched	0		ns
Data Read	Cycle	•	-		
t <sub>RLRH</sub>	28	RD pulse width	(V7 * t <sub>C</sub> ) - 10		ns
t <sub>LLRL</sub>	28	ALE de-asserted to RD asserted	$(t_{\rm C}/2) - 7$		ns
t <sub>AVDVA</sub>	28	Address valid to data input valid, ALE cycle (access time)		(V6 * t <sub>C</sub> ) – 36	ns
t <sub>AVDVB</sub>	29	Address valid to data input valid, non-ALE cycle (access time)		(V5 * t <sub>C</sub> ) – 29	ns
t <sub>RLDV</sub>	28	RD low to valid data in (enable time)		(V7 * t <sub>C</sub> ) – 29	ns
t <sub>RHDX</sub>	28	Data hold time after RD de-asserted	0		ns
t <sub>RHDZ</sub>	28	Bus 3-State after RD de-asserted (disable time)		t <sub>C</sub> – 8	ns
t <sub>DXUA</sub>	28	Hold time of unlatched part of address after data latched	0		ns
Data Write	Cycle		_		
t <sub>WLWH</sub>	30	WR pulse width	(V8 * t <sub>C</sub> ) – 10		ns
t <sub>LLWL</sub>	30	ALE falling edge to WR asserted	(V12 * t <sub>C</sub> ) – 10		ns
t <sub>QVWX</sub>	30	Data valid before WR asserted (data set-up time)	(V13 * t <sub>C</sub> ) – 22		ns
t <sub>WHQX</sub>	30	Data hold time after WR de-asserted (Note 6)	(V11 * t <sub>C</sub> ) – 5		ns
t <sub>AVWL</sub>	30	Address valid to WR asserted (address set-up time) (Note 5)	(V9 * t <sub>C</sub> ) – 22		ns
t <sub>UAWH</sub>	30	Hold time of unlatched part of address after $\overline{\text{WR}}$ is de-asserted	(V11 * t <sub>C</sub> ) - 7		ns
Wait Input					
t <sub>WTH</sub>	31	WAIT stable after bus strobe (RD, WR, or PSEN) asserted		(V10 * t <sub>C</sub> ) – 30	ns
t <sub>WTL</sub>	31	WAIT hold after bus strobe (RD, WR, or PSEN) asserted	(V10 * t <sub>C</sub> ) – 5		ns

NOTES ON PAGE 41.

38 2000 Dec 01

XA-S3

# AC ELECTRICAL CHARACTERISTICS (5 V RANGE) (continued)

This set of parameters is referenced to the XA-S3 clock output.

SYMBOL	FIGURE	PARAMETER	LIN	MITS	_ UNIT
STMBUL	FIGURE	PARAMETER	MIN	MAX	
Address C	ycle				
tCHLH	26	CLKOUT rising edge to ALE rising edge	-	13	ns
t <sub>CLLL</sub>	26	CLKOUT falling edge to ALE falling edge	-	9	ns
t <sub>CHAV</sub>	26	CLKOUT rising edge to address valid	-	18	ns
t <sub>CHAX</sub>	26	CLKOUT rising edge to address changing (hold time)	2	-	ns
Code Read	l Cycle		-		
t <sub>CHPL</sub>	26	CLKOUT rising edge to PSEN asserted	-	14	ns
t <sub>CHPH</sub>	26	CLKOUT rising edge to PSEN de-asserted	-	12	ns
t <sub>IVCH</sub>	26	Instruction valid to CLKOUT rising edge (setup time)	20	-	ns
t <sub>CHIX</sub>	26	CLKOUT rising edge to instruction changing (hold time)	0	-	ns
t <sub>CHIZ</sub>	26	CLKOUT rising edge to Bus 3-State (code read)	-	t <sub>C</sub> -8	ns
Data Read	Cycle		-		
t <sub>CHRL</sub>	28	CLKOUT rising edge to RD asserted	_	12	ns
tCHRH	28	CLKOUT rising edge to RD de-asserted	-	10	ns
t <sub>DVCH</sub>	28	Data valid to CLKOUT rising edge (setup time)	20	-	ns
t <sub>CHDX</sub>	28	CLKOUT rising edge to Data changing (hold time)	0	-	ns
t <sub>CHDZ</sub>	28	CLKOUT rising edge to Bus 3-State (data read)	-	t <sub>C</sub> -8	ns
Data Write	Cycle				
t <sub>CHWL</sub>	30	CLKOUT falling edge to WR asserted	_	12	ns
tchwh	30	CLKOUT rising edge to WR de-asserted	-	10	ns
tqvch	30	Data valid to CLKOUT rising edge (setup time)	4	-	ns
t <sub>CHQX</sub>	30	CLKOUT rising edge to Data changing (hold time)	0	-	ns
Wait Input	-		-	-	-
t <sub>CHWTH</sub>	31	WAIT valid prior to CLKOUT rising edge <sup>8</sup>	21	4	ns

NOTES ON PAGE 41.

XA-S3

# AC ELECTRICAL CHARACTERISTICS (3 V)

 $V_{DD}$  = 2.7 V to 4.5 V;  $T_{amb}$  = 0 to +70°C for commercial,  $T_{amb}$  = -40°C to +85°C for industrial.

CVMPO	FIGURE	DADAMETER	LIM	ITS	UNIT
SYMBOL	FIGURE	PARAMETER	MIN	MAX	UNII
Address C	ycle				
t <sub>LHLL</sub>	26, 28, 30	ALE pulse width (programmable)	(V1 * t <sub>C</sub> ) – 10		ns
t <sub>AVLL</sub>	26, 28, 30	Address valid to ALE de-asserted (set-up)	(V1 * t <sub>C</sub> ) – 18		ns
t <sub>LLAX</sub>	26, 28, 30	Address hold after ALE de-asserted	(t <sub>C</sub> /2) – 12		ns
Code Read	l Cycle				
t <sub>PLPH</sub>	26	PSEN pulse width	(V2 * t <sub>C</sub> ) – 12		ns
t <sub>LLPL</sub>	26	ALE de-asserted to PSEN asserted	(t <sub>C</sub> /2) – 9		ns
t <sub>AVIVA</sub>	26	Address valid to instruction valid, ALE cycle (access time)		(V3 * t <sub>C</sub> ) – 58	ns
t <sub>AVIVB</sub>	27	Address valid to instruction valid, non-ALE cycle (access time)		(V4 * t <sub>C</sub> ) – 52	ns
t <sub>PLIV</sub>	26	PSEN asserted to instruction valid (enable time)		(V2 * t <sub>C</sub> ) – 52	ns
t <sub>PHIX</sub>	26	Instruction hold after PSEN de-asserted	0		ns
t <sub>PHIZ</sub>	26	Bus 3-State after PSEN de-asserted		t <sub>C</sub> – 8	ns
t <sub>IXUA</sub>	26	Hold time of unlatched part of address after instruction latched	0		ns
Data Read	Cycle	•			
t <sub>RLRH</sub>	28	RD pulse width	(V7 * t <sub>C</sub> ) – 12		ns
t <sub>LLRL</sub>	28	ALE de-asserted to RD asserted	$(t_{\rm C}/2) - 9$		ns
t <sub>AVDVA</sub>	28	Address valid to data input valid, ALE cycle (access time)		(V6 * t <sub>C</sub> ) – 58	ns
t <sub>AVDVB</sub>	29	Address valid to data input valid, non-ALE cycle (access time)		(V5 * t <sub>C</sub> ) – 52	ns
t <sub>RLDV</sub>	28	RD low to valid data in (enable time)		(V7 * t <sub>C</sub> ) – 52	ns
t <sub>RHDX</sub>	28	Data hold time after RD de-asserted	0		ns
t <sub>RHDZ</sub>	28	Bus 3-State after RD de-asserted (disable time)		t <sub>C</sub> – 8	ns
t <sub>DXUA</sub>	28	Hold time of unlatched part of address after data latched	0		ns
Data Write	Cycle				
t <sub>WLWH</sub>	30	WR pulse width	(V8 * t <sub>C</sub> ) – 12		ns
t <sub>LLWL</sub>	30	ALE falling edge to WR asserted	(V12 * t <sub>C</sub> ) – 10		ns
t <sub>QVWX</sub>	30	Data valid before WR asserted (data set-up time)	(V13 * t <sub>C</sub> ) – 28		ns
t <sub>WHQX</sub>	30	Data hold time after WR de-asserted (Note 6)	(V11 * t <sub>C</sub> ) – 8		ns
t <sub>AVWL</sub>	30	Address valid to WR asserted (address set-up time) (Note 5)	(V9 * t <sub>C</sub> ) – 28		ns
t <sub>UAWH</sub>	30	Hold time of unlatched part of address after WR is de-asserted	(V11 * t <sub>C</sub> ) – 10		ns
Nait Input	•				
t <sub>WTH</sub>	31	WAIT stable after bus strobe (RD, WR, or PSEN) asserted		(V10 * t <sub>C</sub> ) – 40	ns
t <sub>WTL</sub>	31	WAIT hold after bus strobe (RD, WR, or PSEN) asserted	(V10 * t <sub>C</sub> ) – 5		ns

**NOTES ON PAGE 41.** 

XA-S3

## AC ELECTRICAL CHARACTERISTICS (3 V RANGE) (continued)

This set of parameters is referenced to the XA-S3 clock output.

SYMBOL	FIGURE	PARAMETER	LIN	NITS	UNIT
STMBOL	FIGURE	PARAMETER	MIN	MAX	וואט
Address C	ycle		•		
tCHLH	26	CLKOUT rising edge to ALE rising edge	-	15	ns
t <sub>CLLL</sub>	26	CLKOUT falling edge to ALE falling edge	-	11	ns
t <sub>CHAV</sub>	26	CLKOUT rising edge to address valid	-	29	ns
t <sub>CHAX</sub>	26	CLKOUT rising edge to address changing (hold time)	2	-	ns
Code Read	Cycle		•		-
t <sub>CHPL</sub>	26	CLKOUT rising edge to PSEN asserted	-	16	ns
t <sub>CHPH</sub>	26	CLKOUT rising edge to PSEN de-asserted	-	15	ns
t <sub>IVCH</sub>	26	Instruction valid to CLKOUT rising edge (setup time)	30	-	ns
t <sub>CHIX</sub>	26	CLKOUT rising edge to instruction changing (hold time)	0	-	ns
t <sub>CHIZ</sub>	26	CLKOUT rising edge to Bus 3-State (code read)	-	t <sub>C</sub> -8	ns
Data Read	Cycle	•	•		•
t <sub>CHRL</sub>	28	CLKOUT rising edge to RD asserted	_	20	ns
tCHRH	28	CLKOUT rising edge to RD de-asserted	_	16	ns
tDVCH	28	Data valid to CLKOUT rising edge (setup time)	28		ns
tCHDX	28	CLKOUT rising edge to Data changing (hold time)	0		ns
t <sub>CHDZ</sub>	28	CLKOUT rising edge to Bus 3-State (data read)	_	t <sub>C</sub> -8	ns
Data Write	Cycle		•	•	•
t <sub>CHWL</sub>	30	CLKOUT falling edge to WR asserted	_	19	ns
t <sub>CHWH</sub>	30	CLKOUT rising edge to WR de-asserted	_	16	ns
tQVCH	30	Data valid to CLKOUT rising edge (setup time)	4	-	ns
t <sub>CHQX</sub>	30	CLKOUT rising edge to Data changing (hold time)	0	-	ns
Wait Input		•	•	•	-
t <sub>CHWTH</sub>	31	WAIT valid prior to CLKOUT rising edge <sup>8</sup>	30	4	ns

## NOTES:

- Load capacitance for all outputs = 50 pF.
- Variables V1 through V13 reflect programmable bus timing, which is programmed via the Bus Timing registers (BTRH and BTRL). Refer to the XA User Guide for details of the bus timing settings.
  - V1) This variable represents the programmed width of the ALE pulse as determined by the ALEW bit in the BTRL register. V1 = 0.5 if the ALEW bit = 0, and 1.5 if the ALEW bit = 1.
  - V2) This variable represents the programmed width of the PSEN pulse as determined by the CR1 and CR0 bits or the CRA1, CRA0, and ALEW bits in the BTRL register.
    - For a bus cycle with no ALE, V2 = 1 if CR1/0 = 00, 2 if CR1/0 = 01, 3 if CR1/0 = 10, and 4 if CR1/0 = 11. Note that during burst
      mode code fetches, PSEN does not exhibit transitions at the boundaries of bus cycles. V2 still applies for the purpose of
      determining peripheral timing requirements.
    - For a bus cycle with an ALE, V2 = the total bus cycle duration (2 if CRA1/0 = 00, 3 if CRA1/0 = 01, 4 if CRA1/0 = 10, and 5 if CRA1/0 = 11) minus the number of clocks used by ALE (V1 + 0.5) = 2.
       Example: if CRA1/0 = 10 and ALEW = 1, the V2 = 4 (1.5 + 0.5) = 2.
  - V3) This variable represents the programmed length of an entire code read cycle **with** ALE. This time is determined by the CRA1 and CRA0 bits in the BTRL register. V3 = the total bus cycle duration (2 if CRA1/0 = 00, 3 if CRA1/0 = 01, 4 if CRA1/0 = 10, and 5 if CRA1/0 = 11).
  - V4) This variable represents the programmed length of an entire code read cycle with **no** ALE. This time is determined by the CR1 and CR0 bits in the BTRL register. V4 = 1 if CR1/0 = 00, 2 if CR1/0 = 01, 3 if CR1/0 = 10, and 4 if CR1/0 = 11.
  - V5) This variable represents the programmed length of an entire data read cycle with **no** ALE. This time is determined by the DR1 and DR0 bits in the BTRH register. V5 = 1 if DR1/0 = 00, 2 if DR1/0 = 01, 3 if DR1/0 = 10, and 4 if DR1/0 = 11.
  - V6) This variable represents the programmed length of an entire data read cycle **with** ALE. The time is determined by the DRA1 and DRA0 bits in the BTRH register. V6 = the total bus cycle duration (2 if DRA1/0 = 00, 3 if DRA1/0 = 01, 4 if DRA1/0 = 10, and 5 if DRA1/0 = 11).

Philips Semiconductors Preliminary specification

XA 16-bit microcontroller 32 K/1 K OTP/ROM/ROMless, 8-channel 8-bit A/D, low voltage (2.7 V–5.5 V), I<sup>2</sup>C, 2 UARTs, 16 MB address range

XA-S3

- V7) This variable represents the programmed width of the RD pulse as determined by the DR1 and DR0 bits or the DRA1, DRA0 in the BTRH register, and the SLEW bit in the BTRL register. Note that during a 16-bit operation on an 8-bit external bus, RD remains low and does not exhibit a transition between the first and second byte bus cycles. V7 still applies for the purpose of determining peripheral timing requirements. The timing for the first byte is for a bus cycle with ALE, the timing for the second byte is for a bus cycle with no ALE.
  - For a bus cycle with **no** ALE, V7 = 1 if DR1/0 = 00, 2 if DR1/0 = 01, 3 if DR1/0 = 10, and 4 if DR1/0 = 11.
  - For a bus cycle with an ALE, V7 = the total bus cycle duration (2 if DRA1/0 = 00, 3 if DRA1/0 = 01, 4 if DRA1/0 = 10, and 5 if DRA1/0 = 11) minus the number of clocks used by ALE (V1 + 0.5).
    Example: if DRA1/0 = 00 and ALEW = 0, then V7 = 2 (0.5 + 0.5) = 1.
- V8) This variable represents the programmed width of the WRL and/or WRH pulse as determined by the WM1 bit in the BTRL register. V8 = 1 if WM1 = 0, and 2 if WM1 = 1.
- V9) This variable represents the programmed address setup time for a write as determined by the data write cycle duration (defined by DW1 and DW0 or the DWA1 and DWA0 bits in the BTRH register), the WM0 bit in the BTRL register, and the value of V8.
  - For a bus cycle with an ALE, V9 = the total bus write cycle duration (2 if DWA1/0 = 00, 3 if DWA1/0 = 01, 4 if DWA1/0 = 10, and 5 if DWA1/0 = 11) minus the number of clocks used by the WRL and/or WRH pulse (V8) minus the number of clocks used by data hold time (0 if WM0 = 0 and 1 if WM0 = 1).
    Example: If DWA1/0 = 10, WM0 = 1, and WM1 = 1, then V9 = 4 1 2 = 1.
  - For a bus cycle with **no** ALE, V9 = the total bus cycle duration (2 if DW1/0 = 00, 3 if DW1/0 = 01, 4 if DW1/0 = 10, and 5 if DW1/0 = 11) minus the number of clocks used by the WRL and/or WRH pulse (V8), minus the number of clocks used by data hold time (0 if WMo = 0 and 1 if WM0 = 1).
    Example: If DW1/0 = 11, WM0 = 1, and WM1 = 0, then V9 = 5 1 1 = 3.
- V10) This variable represents the length of a bus strobe for calculation of WAIT set-up and hold times. The strobe may be RD (for data read cycles), WRL and/or WRH (for data write cycles), or PSEN (for code read cycles), depending on the type of bus cycle being widened by WAIT. V10 = 2 for WAIT associated with a code read cycle using PSEN. V10 = V8 for a data write cycle using WRL and/or WRH. V10 = V7 1 for a data read cycle using RD. This means that a single clock data read cycle cannot be stretched using WAIT. If WAIT is used to vary the duration of data read cycles, the RD strobe width must be set to be at least two clocks in duration. Also see Note 4.
- V11) This variable represents the programmed write hold time as determined by the WM0 bit in the BTRL register. V11 0 if the WM0 bit = 0, and 1 if the WM0 bit = 1.
- V12) this variable represents the programmed period between the end of the ALE pulse and the beginning of the WRL and/or WRH pulse as determined by the data write cycle duration (defined by the DWA1 and DWA0 bits in the BTRH register), the WM0 bit in the BTRL register, and the values of V1 and V8. V12 = the total bus cycle duration (2 if DWA1/0 = 00, 3 if DWA1/0 = 01, 4 if DWA1/0 = 10, and 5 if DWA1/0 = 11) minus the number of clocks used by the WRL and/or WRH pulse (V8), minus the number of clocks used by data hold time (0 if WM0 = 0 and 1 if WM0 = 1), minus the width of the ALE pulse (V1).

  Example: If SWA1/0 = 11, WM0 = 1, WM1 = 0, and ALEW = 1, then V12 = 5 1 1 1.5 = 1.5.
- V13) This variable represents the programmed data setup time for a write as determined by the data write cycle duration (defined by DW1 and DW0 or the DWA1 and DWA0 bits in the BTRH register), the WM0 bit in the BTRL register, and the values of V1 and V8.
  - For a bus cycle with an ALE, V13 = the total bus cycle duration (2 if DWA1/0 = 00, 3 if DWA1/0 = 01, 4 if DWA1/0 = 10, and 5 if DWA1/0 = 11) minus the number of clocks used by the WRL and/or WRH pulse (V8), minus the number of clocks used by data hold time (0 if WM0 = 0 and 1 if WM0 = 1), minus the number of clocks used by ALE (V1 + 0.5).
    Example: If DWA1/0 = 11, WM0 = 1, WM1 = 1, and ALEW = 0, then V13 = 5 1 2 1 = 1.
  - For a bus cycle with **no** ALE, V13 = the total bus cycle duration (2 if DW1/0 = 00, 3 if DW1/0 = 01, 4 if DW1/0 = 10, and 5 if DW1/0 = 11) minus the number of clocks used by the WRL and/or WRH pulse (V8), minus the number of clocks used by data hold time (0 if WM0 = 0 and 1 if WM0 = 1).
    Example: If DW1/0 = 01, WM0 = 1, and WM1 = 0, then V13 = 3 1 1 = 1.
- 3. Not all combinations of bus timing configuration values result in valid bus cycles. Please refer to the XA User Guide section on the External Bus for details.
- 4. When code is being fetched for execution on the external bus, a burst mode fetch is used that dows not have PSEN edges in every fetch cycle. This would be A3–A0 for an 8-bit bus, and A3–A1 for a 16-bit bus. Also, a 16-bit read operation conducted on an 8-bit wide bus similarly does not include two separate RD strobes. So, a rising edge on the low order address line (A0) must be used to trigger a WAIT in the second half of such a cycle.
- 5. This parameter is provided for peripherals that have the data clocked in on the falling edge of the WR strobe. This is not usually the case and in most applications this parameter is not used.
- 6. Please note that the XA-S3 requires that extended data bus hold time (WM0 = 1) to be used with external bus write cycles.
- 7. Applies only to an external clock source, not when a crystal is connected to the XTAL1 and XTAL2 pins.
- 8. WAIT should not change between these times.

XA-S3

## **AC WAVEFORMS**




Figure 26. External Program Memory Read Cycle (ALE Cycle)




Figure 27. External Program Memory Read Cycle (Non-ALE Cycle)

2000 Dec 01 43

Downloaded from <u>Elcodis.com</u> electronic components distributor




Figure 28. External Data Memory Read Cycle (ALE Cycle)




Figure 29. External Data Memory Read Cycle (Non-ALE Cycle)




Figure 30. External Data Memory Write Cycle




Figure 31. WAIT Signal Timing

XA-S3




Figure 32. External Clock Drive




Figure 33. AC Testing Input/Output




Figure 34. Float Waveform




Figure 35. I<sub>DD</sub> Test Condition, Active Mode All other pins are disconnected




Figure 36. I<sub>DD</sub> Test Condition, Idle Mode All other pins are disconnected




Figure 37. I<sub>DD</sub> vs. Frequency Valid only within frequency specification of the device under test.




Figure 38. Clock Signal Waveform for  $I_{DD}$  Tests in Active and Idle Modes  $t_{CLCH} = t_{CHCL} = 5 \text{ ns}$ 




Figure 39.  $I_{DD}$  Test Condition, Power Down Mode All other pins are disconnected.  $V_{DD}$ =2 V to 5.5 V

XA-S3

#### **EPROM CHARACTERISTICS**

The XA-S3 is programmed by using a modified Improved Quick-Pulse Programming™ algorithm. This algorithm is essentially the same as that used by 80C51 family EPROM parts. However different pins are used for many programming functions.

The XA-S3 contains three signature bytes that can be read and used by an EPROM programming system to identify the device. The signature bytes identify the device as an XA-S3 manufactured by Philips.

## **Security Bits**

With none of the security bits programmed the code in the program memory can be verified. When only security bit 1 is programmed, MOVC instructions executed from external program memory are disabled from fetching code bytes from the internal memory. All further programming of the EPROM is disabled. When security bits 1 and 2 are programmed, in addition to the above, verify mode is disabled. When all three security bits are programmed, all of the conditions above apply and all external program memory execution is disabled. (See Table 6.)

**Table 6. Program Security Bits** 

PF	ROGRAM	LOCK BIT	ΓS	
	SB1	SB2	SB3	PROTECTION DESCRIPTION
1	U	U	U	No Program Security features enabled.
2	Р	U	U	MOVC instructions executed from external program memory are disabled from fetching code bytes from internal memory and further programming of the EPROM is disabled.
3	Р	Р	U	Same as 2, also verify is disabled.
4	Р	Р	Р	Same as 3, external execution is disabled. Internal data RAM is not accessible.

## NOTES:

- 1. P programmed. U unprogrammed.
- 2. Any other combination of the security bits is not defined.

## **ROM CODE SUBMISSION**

When submitting ROM code for the XA-S3, the following must be specified:

- 1. 32k byte user ROM data
- 2. ROM security bits.

ADDRESS	CONTENT	BIT(S)	COMMENT
0000H to 7FFFH	DATA	7:0	User ROM Data
8020H	SEC	0	ROM Security Bit 1
8020H	SEC	1	ROM Security Bit 2 0 = enable security 1 = disable security
8020H	SEC	3	ROM Security Bit 3 0 = enable security 1 = disable security

2000 Dec 01 48


Downloaded from Elcodis.com electronic components distributor

<sup>™</sup>Trademark phrase of Intel Corporation.

XA-S3

## PLCC68: plastic leaded chip carrier; 68 leads; pedestal

SOT188-3



## DIMENSIONS (millimetre dimensions are derived from the original inch dimensions)

UNIT	Α	A <sub>1</sub> min.	A <sub>3</sub>	A <sub>4</sub> max.	bp	b <sub>1</sub>	D <sup>(1)</sup>	E <sup>(1)</sup>	е	e <sub>D</sub>	еE	H <sub>D</sub>	HE	k	Øj	Lp	v	w	у	Z <sub>D</sub> <sup>(1)</sup> max.	Z <sub>E</sub> <sup>(1)</sup> max.	β
mm	4.57 4.19	0.13	0.25	3.05	0.53 0.33			24.33 24.13	10/	23.62 22.61					15.34 15.19	1.44 1.02	0.18	0.18	0.10	2.06	2.06	45°
inches	0.180 0.165	0.005	0.01	1 0 10 1		0.032 0.026		0.958 0.950		0.930 0.890								0.007	0.004	0.081	0.081	40

## Note


1. Plastic or metal protrusions of 0.01 inches maximum per side are not included.

OUTLINE		REFER	RENCES	EUROPEAN	ISSUE DATE
VERSION	IEC	JEDEC	EIAJ	PROJECTION	ISSUE DATE
SOT188-3	112E10	MO-047			<del>97-12-16</del> 99-12-27

XA-S3

## LQFP80: plastic low profile quad flat package; 80 leads; body 12 x 12 x 1.4 mm

SOT315-1



## **DIMENSIONS (mm are the original dimensions)**

						,													
UNIT	A max.	A <sub>1</sub>	A <sub>2</sub>	A <sub>3</sub>	Ьp	С	D <sup>(1)</sup>	E <sup>(1)</sup>	е	H <sub>D</sub>	HE	L	Lp	v	w	у	Z <sub>D</sub> <sup>(1)</sup>	Z <sub>E</sub> <sup>(1)</sup>	θ
mm	1.6	0.16 0.04	1.5 1.3	0.25	0.27 0.13	0.18 0.12	12.1 11.9	12.1 11.9	0.5	14.15 13.85		1.0	0.75 0.30	0.2	0.15	0.1	1.45 1.05	1.45 1.05	7° 0°

## Note

1. Plastic or metal protrusions of 0.25 mm maximum per side are not included.

OUTLINE		REFER	ENCES	EUROPEAN	ISSUE DATE
VERSION	IEC	JEDEC	EIAJ	PROJECTION	ISSUE DATE
SOT315-1	136E15	MS-026			<del>99-12-27</del> 00-01-19

Philips Semiconductors Preliminary specification

XA 16-bit microcontroller 32 K/1 K OTP/ROM/ROMless, 8-channel 8-bit A/D, low voltage (2.7 V–5.5 V),  $I^2C$ , 2 UARTs, 16 MB address range

XA-S3

## **NOTES**

XA-S3

## Data sheet status

Data sheet status	Product status	Definition [1]
Objective specification	Development	This data sheet contains the design target or goal specifications for product development. Specification may change in any manner without notice.
Preliminary specification	Qualification	This data sheet contains preliminary data, and supplementary data will be published at a later date. Philips Semiconductors reserves the right to make changes at any time without notice in order to improve design and supply the best possible product.
Product specification	Production	This data sheet contains final specifications. Philips Semiconductors reserves the right to make changes at any time without notice in order to improve design and supply the best possible product.

<sup>[1]</sup> Please consult the most recently issued datasheet before initiating or completing a design.

## **Definitions**

**Short-form specification** — The data in a short-form specification is extracted from a full data sheet with the same type number and title. For detailed information see the relevant data sheet or data handbook.

**Limiting values definition** — Limiting values given are in accordance with the Absolute Maximum Rating System (IEC 134). Stress above one or more of the limiting values may cause permanent damage to the device. These are stress ratings only and operation of the device at these or at any other conditions above those given in the Characteristics sections of the specification is not implied. Exposure to limiting values for extended periods may affect device reliability.

**Application information** — Applications that are described herein for any of these products are for illustrative purposes only. Philips Semiconductors make no representation or warranty that such applications will be suitable for the specified use without further testing or modification.

## **Disclaimers**

**Life support** — These products are not designed for use in life support appliances, devices or systems where malfunction of these products can reasonably be expected to result in personal injury. Philips Semiconductors customers using or selling these products for use in such applications do so at their own risk and agree to fully indemnify Philips Semiconductors for any damages resulting from such application.

Right to make changes — Philips Semiconductors reserves the right to make changes, without notice, in the products, including circuits, standard cells, and/or software, described or contained herein in order to improve design and/or performance. Philips Semiconductors assumes no responsibility or liability for the use of any of these products, conveys no license or title under any patent, copyright, or mask work right to these products, and makes no representations or warranties that these products are free from patent, copyright, or mask work right infringement, unless otherwise specified.

Philips Semiconductors 811 East Arques Avenue P.O. Box 3409 Sunnyvale, California 94088–3409 Telephone 800-234-7381 © Copyright Philips Electronics North America Corporation 2000 All rights reserved. Printed in U.S.A.

Date of release: 12-00

Document order number: 9397 750 07816

Let's make things better.

Philips Semiconductors



